

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
762	*	MOULTRIE	14	8

CONTRACT NO. 70460
• D-5 CONTRACT MAINT 2005-12

PARTIAL DEPTH PATCHING (Cont.)

STATION	LANE	LENGTH (ft)	WIDTH (ft)	PARTIAL DEPTH REMOVAL X4401705	BIT MIX FOR PATCHING Z0004800
				(sq. yd)	(Ton)
244+96	SB	8	12	10.7	2.7
245+34	SB	4	12	5.3	1.3
246+32	SB	4	12	5.3	1.3
246+90	SB	4	12	5.3	1.3
247+26	SB	4	12	5.3	1.3
247+57	SB	4	12	5.3	1.3
248+48	SB	4	12	5.3	1.3
248+76	SB	8	12	10.7	2.7
250+60	SB	10	12	13.3	3.4
251+04	SB	4	12	5.3	1.3
254+37	SB	20	12	26.7	6.7
254+58	SB	4	12	5.3	1.3
255+23	SB	4	12	5.3	1.3
255+53	SB	8	12	10.7	2.7
255+98	SB	4	12	5.3	1.3
256+04	SB	20	12	26.7	6.7
256+25	SB	4	12	5.3	1.3
257+35	SB	6	12	8.0	2.0
258+00	SB	4	12	5.3	1.3
258+36	SB	8	12	10.7	2.7
260+27	SB	8	12	10.7	2.7
260+57	SB	4	12	5.3	1.3
261+39	SB	10	12	13.3	3.4
262+93	SB	10	12	13.3	3.4
262+32	SB	4	12	5.3	1.3
263+32	SB	4	12	5.3	1.3
263+59	SB	4	12	5.3	1.3
265+74	SB	6	12	8.0	2.0
265+94	SB	4	12	5.3	1.3
265+96	SB	8	12	10.7	2.7
268+62	SB	4	12	5.3	1.3
269+49	SB	4	12	5.3	1.3
			SB TOTALS	381.3	96.4
			JOB TOTALS	868.0 (sq. yd)	218.7 (Ton)