

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
762	•	MOULTRIE	14	9

CONTRACT NO. 70460  
• D-5 CONTRACT MAINT 2005-12

## FULL DEPTH PATCHING

STATION	LANE	LENGTH (ft)	WIDTH (ft)	CL. D TYPE II, 10" 44201765 (sq. yd)
230+85	NB	8	12	10.7
250+38	NB	5	12	6.7
259+92	NB	6	12	8.0
264+90	NB	8	12	10.7
266+66	NB	6	12	8.0
NB TOTAL				44.1
229+66	SB	6	12	8.0
229+83	SB	4	12	5.3
230+85	SB	8	12	10.7
250+38	SB	5	12	6.7
259+92	SB	6	12	8.0
266+66	SB	6	12	8.0
SB TOTAL				46.7
TOTAL = 90.8				(sq. yd)