

SUMMARY OF QUANTITIES			SFTY-2A		
CODE NO.	ITEM	UNIT	100% STATE		
			TOTAL QTY	SN 086-0023	SN 086-0024
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.6	0.8	0.8
40600300	AGGREGATE (PRIME COAT)	TON	2	1	1
40600990	TEMPORARY RAMP	SQ YDS	73.4	36.7	36.7
44000006	BITUMINOUS SURFACE REMOVAL, 1 1/2"	SQ YDS	786	393	393
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YDS	942	471	471
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YDS	3412	1706	1706
48101200	AGGREGATE SHOULDERS, TYPE B	TONS	44	22	22
48202000	BITUMINOUS SHOULDER SUPERPAVE	TONS	16	8	8
48202800	BITUMINOUS SHOULDER SUPERPAVE, 10"	SQ YDS	3412	1706	1706
50300260	BRIDGE DECK GROOVING	SQ YDS	892	446	446
50300530	FLOOR DRAIN EXTENSIONS	EACH	10	5	5
60260100	INLETS TO BE ADJUSTED	EACH	2	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1.5	1.5
67100100	MOBILIZATION	L SUM	1	1	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	0.5	0.5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.5	0.5

Rev.

QUANTITIES  
 FAI 72 (I-72)  
 SECTION (86-10B)I-1  
 SCOTT COUNTY