

S U M M A R Y O F Q U A N T I T I E S

SFTY-2A

CODE NO.	ITEM	UNIT	100% STATE		
			TOTAL QTY	SN 086-0023	SN 086-0024
70300530	PAVEMENT MARKING TAPE, TYPE III, 5 IN	FEET	4040	2020	2020
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1684	842	842
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FEET	4174	2087	2087
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1684	842	842
X0320887	POLYMER CONCRETE	CU FT	12.4	6.2	6.2
X0321468	PLUG EXISTING DECK DRAINS	EACH	18	9	9
X0321744	SILICONE JOINT SEALER 2"	FEET	178	89	89
X0324401	PORTABLE TEMPORARY BARRIER SYSTEM, TL-3	FEET	600	300	300
X0324402	RELOCATE PORTABLE TEMPORARY BARRIER SYSTEM, TL-3	FEET	600	300	300
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TONS	50	25	25
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2½"	SQ YDS	942	471	471
Z0006201	BRIDGE DECK HYDRO-SCARIFIATION 1"	SQ YDS	942	471	471
Z0015595	DECK DRAIN EXTENSIONS	EACH	18	9	9
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YDS	7.52	3.98	3.54
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YDS	12.01	5.12	6.89

* SPECIALTY ITEMS

Rev.

QUANTITIES
 FAI 72 (I-72)
 SECTION (86-10B)I-1
 SCOTT COUNTY