

SUMMARY OF QUANTITIES

FIP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
9230	68WRS	MONROE	35	3
STA.		TO STA.		
CONTRACT NO.: 76792				

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL		CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	QUANTITIES	1000-1A			
20200100	EARTH EXCAVATION	CU YD	451	451			
20800150	TRENCH BACKFILL	CU YD	25	25			
25000110	SEEDING, CLASS 1A	ACRE	0.75	0.75			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26	26			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26	26			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26	26			
25100115	MULCH, METHOD 2	ACRE	0.75	0.75			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	36	36			
28000300	TEMPORARY DITCH CHECKS	EACH	29	29			
28000400	PERIMETER EROSION BARRIER	FOOT	608	608			
28000500	INLET AND PIPE PROTECTION	EACH	13	13			
28100109	STONE RIPRAP, CLASS A5	SQ YD	73	73			
28200200	FILTER FABRIC	SQ YD	73	73			
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	2483	2483			
35800100	PREPARATION OF BASE	SQ YD	164	164			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.2	2.2			
40600300	AGGREGATE (PRIME COAT)	TON	10.2	10.2			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	205	205			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	50	50			
40600990	TEMPORARY RAMP	SQ YD	106	106			
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3			
40800030	AGGREGATE (PRIME COAT)	TON	0.7	0.7			
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	68	68			
44000100	PAVEMENT REMOVAL	SQ YD	158	158			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	243	243			
44004250	PAVED SHOULDER REMOVAL	SQ YD	1078	1078			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3046	3046			
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	18	18			
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	295	295			
50105220	PIPE CULVERT REMOVAL	FOOT	164	164			
54213450	END SECTIONS 15"	EACH	6	6			
54213453	END SECTIONS 18"	EACH	1	1			
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	98	98			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	120	120			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	195	195			
55100900	STORM SEWER REMOVAL 18"	FOOT	269	269			

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL		CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	QUANTITIES	1000-1A			
60219510	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 20 FRAME AND GRATE	EACH	1	1			
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	1	1			
60500060	REMOVING INLETS	EACH	3	3			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3.2	3.2			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	435	435			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	130	130			
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	19	19			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	491	491			
70300200	TEMPORARY PAVEMENT MARKING	FOOT	26376	26376			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1000	1000			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2505	2505			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	12	12			
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	36	36			
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	27.5	27.5			
* 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	16	16			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	47	47			
* 73000100	WOOD SIGN SUPPORT	FOOT	85	85			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYM3OLS	SQ FT	250	250			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6594	6594			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	82	82			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	38	38			
X3560150	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 11 INCH	SQ YD	1624	1624			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	536	536			
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	254	254			
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	52	52			

* SPECIALTY ITEMS

PLOT DATE: Tuesday February 08, 2005 @ 3:03:58 PM

SUMMARY OF QUANTITIES - FAU 9320 (IL 003)