STATION	SIDE	MANHOLES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	INLETS TO BE ADJUSTED WITH NEW TYPE 3V FRAME AND GRATE	VALVE BOX FRAMES TO BE ADJUSTED
		EACH	EACH	EACH	EACH	EACH
1+65.60	RT					1
1+70.50	RT					1
2+25.60	LT	1				
4+65.80	LT	1				
4+84.91	RT	1				
8+69.00	RT					1
8+73.21	LT			1		
8+85.50	LT					1
9+07.00	CL	1				
9+21.11	LT. & RT.			2		
12+03.50	RT				1	
12+34.00	CL	1				
12+82.00	LT					1
15+33.00	CL		1			
16+16.50	RT					1
18+87.00	CL		1			
19+02.50	RT					1
21+48.00	LT					1
21+71.00	RT	1				
21+73.00	LT	1				
21+99.25	RT			1		
22+83.00	CL	1				
23+48.50	CL		1			
23+84.00	LT					1
24+78.00	CL	1				
25+09.00	LT					1
25+14.00	RT			1		
25+27.00	LT					1
25+31.00	LT	1				1
26+32.00	CL		1			
27+00.21	RT			1		
27+80.68	RT			1		
28+00.00	RT					1
28+14.00	CL		1			
29+14.50	RT			1		
31+00.00	LT					1
31+03.00	LT	1				
31+50.46	LT			1		
31+65.97	RT			1		
32+13.56	CL	1				
32+52.20	RT			1		
32+91.57	RT			1		
33+93.00	CL	1				
34+85.00	LT	1				
36+13.00	CL	1				
37+67.00	RT		1			
38+09.00	CL	1				
39+20.00	LT					1
39+60.00	CL	1				
41+96.00	LT					1
42+01.00	LT					1
42+22.00	CL	1				
42+67.00	RT	1				
45+00.00	LT					1
45+19.00	CL	1				
47+44.00	CL	1				
48+33.00	LT					1
48+43.00	LT					1
49+99.00	CL	1				
53+05.00	RT	1				
301+59.00	LT	1				
400+52.69	RT			1		
	TOTAL	24	6	13	1	20

STATION	TO STATION	SIDE	STORM SEWER REMOVAL 24"	STORM SEWER REMOVAL 30"	REMOVING INLETS	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	PIPE DRAINS 4" (SPECIAL)	MANHOLES, TYPE A, SPECIAL, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	INLETS, TYPE A, TYPE 8 GRATE	INLETS, SPECIAL, WITH TYPE 7 GRATE	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	TRENCH BACKFILL
			FOOT	FOOT	EACH	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	TON
2+64.71		RT.											1	1.1
13+77.00		LT.											1	1.1
33+55.00	33+55.00	LT.							3					
33+55.00	34+62.00	LT.							107					
26+48.00		RT.	19	21			14	17		1				
33+10.00		RT.			1	6					1			2.9
8+84.00		RT.										1		
2+64.71		RT.			1									
13+77.00		LT.			1									
		TOTAL	19	21	3	6	14	17	110	1	1	1	2	5.1

STATION	TO STATION	SIDE	DOMESTIC METER VAULTS TO BE MOVED	REMOVING MANHOLES	SANITARY SEWER REMOVAL, 8"	SANITARY SEWER REMOVAL AND REPLACEMENT 12"	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	SANITARY SEWER, PVC, 8"	SANITARY SEWER SERVICE 6"	FIRE HYDRANTS TO BE RELOCATED	TRENCH BACKFILL
			EACH	EACH	FOOT	FOOT	EACH	FOOT	FOOT	EACH	TON
4+95.00		RT.							40		43.0
8+82.50	9+07.00	LT.				25					3.8
8+89.50		LT.		1	10		1	10			1.0
13+83.70		LT.								1	7.6
14+27.50	14+37.50	C.L.				10			10		7.0
19+34.50	19+69.50	C.L.				35					35.1
21+43.80		LT.								1	7.4
22+04.00		LT.	1								
26+32.10		RT.		1							
		TOTAL	1	2	10	70	1	10	50	2	104.9

STATION	TO STATION	SIDE	SEEDING, CLASS 1	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 1	TEMPORARY EROSION CONTROL SEEDING
			ACRE	POUND	POUND	POUND	ACRE	POUND
1+00	2+50	LT.	0.03	2.8	2.8	2.8	0.03	3.1
2+50	4+00	LT.	0.02	2.0	2.0	2.0	0.02	2.2
4+00	7+00	LT.	0.04	3.7	3.7	3.7	0.04	4.1
7+00	9+50	LT.	0.05	4.1	4.1	4.1	0.05	4.6
9+50	13+00	LT.	0.06	5.1	5.1	5.1	0.06	5.6
13+00	19+00	LT.	0.10	8.7	8.7	8.7	0.10	9.6
19+00	22+00	LT.	0.03	3.1	3.1	3.1	0.03	3.4
22+00	31+50	LT.	0.17	15.7	15.7	15.7	0.17	17.4
31+50	33+00	LT.	0.01	1.2	1.2	1.2	0.01	1.4
1+00	3+00	RT.	0.01	1.2	1.2	1.2	0.01	1.4
3+00	7+00	RT.	0.04	3.3	3.3	3.3	0.04	3.7
7+00	19+00	RT.	0.14	12.4	12.4	12.4	0.14	13.8
19+00	21+50	RT.	0.01	0.8	0.8	0.8	0.01	0.9
21+50	26+00	RT.	0.05	4.6	4.6	4.6	0.05	5.2
26+00	33+00	RT.	0.14	13.0	13.0	13.0	0.14	14.5
33+00	52+60	RT.	0.31	28.3	28.3	28.3	0.31	31.5
		TOTAL	1.21	110.0	110.0	110.0	1.21	122.4

STATION	OFFSET	TREE REMOVAL
		UNIT
8+80	30' RT.	18
8+82.50	30' RT.	18
8+86.50	31' RT.	24
22+09	29.5' RT.	24
	TOTAL	84

DRAWN BY D.B.H.
CHECKED BY M.G.M.
APPROVED BY W.J.S.
DATE FEBRUARY 24, 2005

REVISIONS
DATE | BY

SCHEDULE OF QUANTITIES
EAST GRANT STREET IMPROVEMENTS

MACOMB, ILLINOIS

BENTON & ASSOCIATES INC
Consulting Engineers / Land Surveyors
1970 West Lafayette Avenue
Jacksonville, Illinois 62650
Phone : 217-245-4146
Fax : 217-245-4149
IL Design Firm Registration No. 184-000852

FIELD BOOK: | SCALE: | JOB NO. 04e1466 | SHEET 11 OF 66