



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2005

SUBJECT: FAP Route 774 (IL 32/33)
Section 107 WRS-1, 107BY-1 & 107B-2
Effingham County
Contract No. 94827
Item No. 123, April 29, 2005 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised sheet 2 of the Plans.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Added pages 178 & 179 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by "P.E." in smaller letters.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Christine Reed; Roger Driskell; R. E. Anderson; Jim White; Design & Environment File

TBW:DB:jc

CURING AND PROTECTION OF CONCRETE CONSTRUCTION (BDE) 122

EPOXY COATING ON REINFORCEMENT (BDE) 129

EPOXY PAVEMENT MARKING (BDE) 129

EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 130

FLAGGER VESTS (BDE) 130

FREEZE-THAW RATING (BDE)..... 131

HAND VIBRATOR (BDE)..... 131

IMPACT ATTENUATORS, TEMPORARY (BDE)..... 131

LIME GRADATION REQUIREMENTS (BDE) 133

MULCHING SEEDED AREAS (BDE) 133

PARTIAL PAYMENTS (BDE)..... 134

PAYMENTS TO SUBCONTRACTORS (BDE) 135

PERSONAL PROTECTIVE EQUIPMENT (BDE) 136

PORTLAND CEMENT (BDE)..... 136

PORTLAND CEMENT CONCRETE (BDE) 136

PRECAST CONCRETE PRODUCTS (BDE)..... 137

RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE) (BDE)..... 138

RAP FOR USE IN BITUMINOUS CONCRETE MIXTURES (BDE)..... 138

SEEDING AND SODDING (BDE)..... 142

SHOULDER STABILIZATION AT GUARDRAIL (BDE)..... 144

SOIL MODIFICATION (BDE)..... 145

STABILIZED SUBBASE AND BITUMINOUS SHOULDERS SUPERPAVE (BDE)..... 150

SUBGRADE PREPARATION (BDE) 155

SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE)..... 155

SUSPENSION OF SLIPFORMED PARAPETS (BDE)..... 162

TEMPORARY CONCRETE BARRIER (BDE) 162

TEMPORARY EROSION CONTROL (BDE) 164

TRAFFIC BARRIER TERMINALS (BDE) 165

TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 166

TRAINING SPECIAL PROVISIONS 167

TRUCK BED RELEASE AGENT (BDE) 170

WEIGHT CONTROL DEFICIENCY DEDUCTION..... 170

WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 172

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)..... 173

STEEL COST ADJUSTMENT (BDE)..... 173

FURNISHED EXCAVATION (BDE) 178

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE) 178

PREFORMED RECYCLED RUBBER JOINT FILLER (BDE)..... 179

FURNISHED EXCAVATION (BDE)

Effective: August 1, 2002

Revised: November 1, 2004

Revise Article 204.01 of the Standard Specifications to read:

Description. Borrow excavation and furnished excavation shall consist of excavating suitable materials obtained from locations approved by the Engineer and transporting the materials to various locations throughout the limits of the contract.”

Revise Article 204.07(b) of the Standard Specifications to read:

“(b) Measured Quantities. Furnished excavation will be computed for payment in cubic meters (cubic yards) as follows:

Furnished Excavation = Embankment - [Suitable Excavation x (1 - Shrinkage Factor)]

Where:

Embankment = the volume of fill in its final position computed by the method of average end areas and based upon the existing ground line as shown on the plans except as noted in (1) and (2) below;

Suitable Excavation = earth excavation, rock excavation, and other on-site excavation suitable for use in embankments as shown in the Earthwork Schedule on the plans;

Shrinkage Factor = 0.25 unless otherwise shown on the plans.

(1) If the Contractor so requests, the Engineer will reestablish the existing ground line after the clearing and tree removal have been performed according to Section 201 and the top 150 mm (6 in.) of the existing ground surface has been disked and compacted to the satisfaction of the Engineer.

(2) If settlement platforms are erected, the Engineer will reestablish the existing ground line after the embankment is complete as specified in Article 204.07(a)(2).

Furnished excavation placed in excess of that required for the execution of the contract will not be measured for payment.”

Add the following paragraph to the end of Article 204.07 of the Standard Specifications:

“The quantity for furnished excavation will not be recalculated when surplus, suitable materials are utilized in embankments according to Article 202.03.”

PLASTIC BLOCKOUTS FOR GUARDRAIL (BDE)

Effective: November 1, 2004

Add the following to Article 630.02 of the Standard Specifications:

Added 04-14-2005

“(h) Plastic Blockouts (Note 1.)

Note 1. Plastic blockouts, 150 mm (6 in.) deep, may be used in lieu of 150 mm (6 in.) deep wood block-outs for steel plate beam guardrail. The plastic blockouts shall be on the Department’s approved list.”

PERFORMED RECYCLED RUBBER JOINT FILLER (BDE)

Effective: November 1, 2002

Revise Article 503.02(c) of the Standard Specifications to read:

“(c) Preformed Expansion Joint Filler 1051”

Revise Article 637.02(d) of the Standard Specifications to read:

“(d) Preformed Expansion Joint Filler 1051”

Add the following Article to Section 1051 of the Standard Specifications:

“1051.10 Preformed Recycled Rubber Joint Filler. Preformed recycled rubber joint filler shall consist of ground tire rubber, free of steel and fabric, combined with ground scrap or waste polyethylene. It shall not have a strong hydrocarbon or rancid odor and shall meet the physical property requirements of ASTM D 1752. Water absorption by volume shall not exceed 5.0 percent.”

Added 04-14-2005