

## SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9195	*	ST CLAIR	54	3
STA.		TO STA.		

\* CITY SECTION #01-00039-00-FP  
 COUNTY SECTION #03-00360-00-PV  
 CONTRACT NO. 97235

CODE NO.	ITEM	UNITS	1000-2A	TOTAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	22	22
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	74	74
20200100	EARTH EXCAVATION	CU YD	5320	5320
20800150	TRENCH BACKFILL	CU YD	278	278
25000100	SEEDING, CLASS 1	ACRE	0.75	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	68
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	68
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	68
25100115	MULCH, METHOD 2	ACRE	0.75	0.75
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150
28000400	PERIMETER EROSION BARRIER	FOOT	454	454
28000500	INLET AND PIPE PROTECTION	EACH	22	22
28100107	STONE RIPRAP, CLASS A4	SQ YD	20	20
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	8774	8774
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	268	268
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	260	260
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2604	2604
40600300	AGGREGATE (PRIME COAT)	TON	156	156
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	390	390
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	259	259
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	9089	9089
44000100	PAVEMENT REMOVAL	SQ YD	5740	5740
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	36	36
50100300	* REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1
50100400	* REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	52	52
542A0259	PIPE CULVERTS, CLASS A, TYPE 1 54"	FOOT	14	14
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	88	88
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2	2
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2	2
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	1	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	916	916
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	280	280
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	163	163
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	211	211
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	115	115

CODE NO.	ITEM	UNITS	1000-2A	TOTAL
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	559	559
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	11	11
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	341	341
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	303	303
55035700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 45, RISE 29	FOOT	33	33
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	7	7
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	8	8
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2	2
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	6	6
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	14	14
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4	4
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	7	7
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	4	4
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	4	4
60500060	REMOVING INLETS	EACH	3	3
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4.8	4.8
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4696.0	4696.0
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	7	7
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4
70101700	* TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	360	360
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	120	120
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2398	2398
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	25	25
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	30	30
XX000714	* FENCE TO BE REMOVED AND RE-ERECTED	FOOT	181	181
XX002093	* REMOVAL OF EXISTING RIPRAP	SQ YD	120	120
XX004949	* INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE	TON	30	30
X4021000	* TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	31	31
X4022000	* TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	8	8
X4066414	* BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	1167	1167
X4066614	* BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	1944	1944
XX006173	* GEOTECHNICAL FABRIC, SPECIAL	L SUM	1	1

\* A CODE NUMBER WITH AN ASTERISK (\*) INDICATES THAT THE PAY ITEM IS NOT COVERED BY THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, THE STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL ITEMS OR BY A HIGHWAY STANDARD. A SPECIAL PROVISION IS REQUIRED FOR CLARIFICATION UNLESS THE ITEM IS COVERED BY SOME OTHER METHOD.

REVISIONS	
NO.	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: NO SCALE  
 DATE: 12-01-04

DRAWN BY: JJC  
 CHECKED BY: MAR

11/17/2005 2:46:16 PM