

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	130 I-2,TS	WILLIAMSON	90	13
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO 98884				

REMOVAL SCHEDULE

LOCATION STATION TO STATION	ISLAND REMOVAL	PAVED SHOULDER REMOVAL	BITUMINOUS SURFACE REMOVAL (VAR. DEPTH)	BITUMINOUS SURFACE REMOVAL 1-1/2"	PAVEMENT REMOVAL	PIPE CULVERT REMOVAL
	SQ FT	SQ YD	SQ YD	SQ YD	SQ YD	FOOT
IL 148						
112+37 TO 119+00			4568			
112+75.9 LT TO 114+01.4 LT					285	
112+76 LT (IL 148) TO 1+59 LT (GRAND ROAD)		68				
113+30.5 RT TO 113+96.2 RT					59	
113+30.5 RT (IL 148) TO 1+19.2 RT (McCREE ROAD)		38				
113+84 LT TO 113+96 LT	90					
114+32.3 RT TO 115+32.9 RT					61	
114+39.3 LT TO 115+18.2 LT					217	
113+75 RT TO 114+46 RT						71
GRAND ROAD						
0+40 TO 2+52.37				897		
1+59 RT (GRAND ROAD) TO 119+00 LT (IL 148)		179				
McCREE ROAD						
1+20.85 LT (McCREE ROAD) TO 115+32.9 RT (IL 148)		55				
1+85 TO 2+00						
TOTALS	90	340	4568	897	622	71

EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	COMMENTS
	CU YD	CU YD	CU YD	CU YD	
IL 148					
112+37 LT TO 113+78 LT	43	32	3	29	
112+37 RT TO 113+67 RT	14	11	4	7	
114+73 LT TO 119+00 LT	178	134	209	-76	
114+64 RT TO 118+25 RT	11	8	4	4	
GRAND ROAD					
0+71 LT TO 2+52.37 LT	36	27	21	6	
0+52 RT TO 2+52.37 RT	50	38	14	24	
McCREE ROAD					
0+49 LT TO 2+00 LT	25	19	51	-32	
0+67 RT TO 2+00 RT	64	48	67	-19	
	421			-57	

Shrinkage Factors: Earth Excavation 25%