

EARTHWORK SCHEDULE

IL RTE. 137	EARTH EXCAVATION (CU. YD)	UNSUITABLE MATERIAL (CU.YD.)	EXCAVATION USED AS EMBANKMENT (SHRINKAGE 15%) (CU.YD.)	EMBANKMENT (CU. YD.)	EARTH WORK BALANCE SURPLUS (+) OR SHORTAGE (-) (CU. YD.)
102+59 TO 112+10.86	305	251	259	386	-127
O'PLAINE RD					
41+62 TO 49+40	202	67	172	10	163
TOTAL	507	318	431	396	35

NOTE:

A THICKNESS OF 6 INCHES OF TOPSOIL STRIPPING SHALL BE USED FOR REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

FILE NAME =	USER NAME = abebawa	DESIGNED - Designed By	REVISED - Revised By1	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL RTE. 137 AT O'PLAINE RD SCHEDULES OF QUANTITIES	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw-work\p\dot\abebawa\d0188337\1142	09-Design.dgn	DRAWN - Drawn By	REVISED - Revised By2			352	56N-4	COOK	50	8	
	PLOT SCALE = 49.9999' / IN.	CHECKED - Checked By	REVISED - Revised By3			SCALE: Scale		SHEET NO. OF SHEETS		STA. TO STA.	
	PLOT DATE = 2/8/2011	DATE - Checked Date	REVISED - Revised By4			FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT	
						CONTRACT NO. 60K19					