



SCHEDULE OF QUANTITIES

ITEM	UNIT	TOTAL
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	860
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	860
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2
TRANSCEIVER - FIBER OPTIC	EACH	1
DRILL EXISTING HANDHOLE	EACH	2
REMOVE EXISTING CABLE FROM CONDUIT	FOOT	9705
ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1/C	FOOT	4825
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	4880
RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1

APEX
CONSULTING ENGINEERS, LLC
111 E. Wacker Drive Suite 520
Chicago, IL 60601

FILE NAME =	USER NAME = *USER#	DESIGNED - WHI	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 137 @ O'PLAINE ROAD INTERCONNECT SCHEMATIC			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILES#		DRAWN - WHI	REVISED -		SCALE: N.T.S.	SHEET NO. OF SHEETS	STA. TO STA.	352	56N-4	LAKE	50	30	
	PLOT SCALE = *SCALE#	CHECKED - DEB	REVISED -										
	PLOT DATE = *DATE#	DATE - 11/08/10	REVISED -										
CONTRACT NO. 60K19													
ILLINOIS FED. AID PROJECT													