

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005						CODE NO	ITEM		UNIT	0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	406	406					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	425	425					
25200110	SODDING, SALT TOLERANT	SO YD	406	406					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	353	353					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	62	62					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	23481	23481					
40600300	AGGREGATE (PRIME COAT)	TON	296	296					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	281	281					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	114	114					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	64315	64315					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500	500					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	365	365					*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	570	570					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6392	6392					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	425	425					
42001300	PROTECTIVE COAT	SO YD	812	812					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	353	353					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	73883	73883					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	880	880					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	796	796					*78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	750	750					
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	123	123					*88600600	DETECTOR LOOP REPLACEMENT	FOOT	668	668					
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	816	816					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	58	58					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	125	125					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3196	3196					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	15	15					#X5539700	STORM SEWERS TO BE CLEANED	FOOT	800	800					
60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE I FRAME, OPEN LID	EACH	2	2					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	13	13					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2435	2435					
67100100	MOBILIZATION	L SUM	1	1					#Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10					
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	11	11					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	205.6	205.6					
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	11	11														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5														
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4275	4275														
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	281	281														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	64315	64315														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	500	500						* SPECIALTY ITEMS								
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	570	570						# NON- PARTICIPATING ITEMS	(10020-27)							

FILE NAME =  
c:\pwr\work\pwr\ofgoban\jr\0194557\0152310-str-plan.rgn

USER NAME = goban jr  
DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL 171 (ARCHER AVENUE)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 3565 SECTION B-R-2-RS COUNTY COOK TOTAL SHEETS 37 SHEET NO. 3

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 60K54