

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 0005					CODE NO	ITEM	UNIT		ROADWAY 0005				
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	67	67					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	195	195				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	264	264					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	151	151				
25200110	SODDING, SALT TOLERANT	SO YD	264	264					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5730	5730				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	181.5	181.5				
40600300	AGGREGATE (PRIME COAT)	TON	158	158					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	31110	31110				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	59	59					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	765	765				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	195	195				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	478	478					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	151	151				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3302	3302					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	560	560				
42001300	PROTECTIVE COAT	SO YD	527	527					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	447	447				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	39316	39316					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	798	798					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	1622	1622				
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	416	416					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1580	1580				
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	175	175					Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	34	34				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	393	393					Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	8	8				
Δ X5539700	STORM SEWERS TO BE CLEANED	FOOT	1400	1400													
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	26	26													
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5													
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	51573	51573													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	181.5	181.5													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31110	31110													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	765	765													

Δ = NON - PARTICIPATING
* SPECIALTY ITEMS