

SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

URBAN
80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	44	44
40600300	AGGREGATE (PRIME COAT)	TON	220	220
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	585	585
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9,515	9,515
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	10	10
42001300	PROTECTIVE COAT	SQ YD	192	192
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	113,250	113,250
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	10	10
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	29	29
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	612	612
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	728	728
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1,544	1,544
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,281	1,281
60618210	HOT-MIX ASPHALT MEDIAN SURFACE, 4 INCH	SQ FT	735	735
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,905	1,905
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	23,000	23,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	984	984
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	64,280	64,280
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,525	2,525
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	330	330
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	625	625
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	510	510
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7,670	7,670
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	984	984
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	64,280	64,280
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,525	2,525
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	330	330
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	625	625
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	510	510

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	775	775
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	775	775
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,558	1,558
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	220	220
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6,342	6,342
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	2,640	2,640
X5539700	STORM SEWERS TO BE CLEANED	FOOT	800	800
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	575	575
Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	5	5
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50	50
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	129	129
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEMS
Δ = Non-participating

COMPANY NAME: SEC Group, Inc.
PROJECT CONTACT: #PROJECT CONTACT
CLIENT: #CLIENT
DATE PLOTTED: 2/14/2011 8:47:09 AM
FILE NAME: 86100196.02-sum.dgn
PLOT DRIVER: pdf.plt
PEN TABLE: standard-trans.tbl



USER NAME = SPernal	DESIGNED - J. ROITBURD	REVISED -
PLOT SCALE = N.T.S.	DRAWN - R. BEST	REVISED -
PLOT DATE = 2/14/2011	CHECKED - T. HAMILTON	REVISED -
	DATE - 2/14/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
ILLINOIS ROUTE 38 (KAUTZ ROAD TO ILLINOIS ROUTE 59)

F.A.P. RTE. 347	SECTION LY-RS-3	COUNTY DUPAGE	TOTAL SHEETS 35	SHEET NO. 3
SCALE: N.T.S.			SHEET NO. 1 OF 1 SHEETS STA. TO STA.	
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		

Rev.

CONTRACT NO. 60K82