

SUMMARY OF QUANTITIES				90% FED. 10% STATE		90% FED. 10% STATE	
ITEM NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	0021 SAFETY	0021 100% VILLAGE OF LAKE ZURICH	0031 LANDSCAPING	0040 STORM SEWERS
20200100	EARTH EXCAVATION	CU YD	327	327			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	376	376			
20800150	TRENCH BACKFILL	CU YD	119	119			
21101615	TOPSOIL, FURNISH AND PLACE, 4"	SQ YD	1,812			1,812	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22			22	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22			22	
25200110	SODDING, SALT TOLERANT	SQ YD	1,812			1,812	
25200200	SUPPLEMENTAL WATERING	UNIT	54			54	
28000400	PERIMETER EROSION BARRIER	FOOT	722	722			
28000510	INLET FILTERS	EACH	18	18			
31101200	SUB BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	516	516			
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	516	516			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	192	192			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	13	13			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	13	13			
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	65	65			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	21	21			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	45	45			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	51	51			
42001300	PROTECTIVE COAT	SQ YD	800	800			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,373	2,373			
42400800	DETECTABLE WARNINGS	SQ FT	50	50			
44000100	PAVEMENT REMOVAL	SQ YD	138	138			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	533	533			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	192	192			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	857	857			
44000600	SIDEWALK REMOVAL	SQ FT	1,895	1,895			
44004250	PAVED SHOULDER REMOVAL	SQ YD	182	182			
44002208	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2"	SQ YD	117	117			
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	99	99			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	4	4			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	250	250			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	52				52
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	77				77
55100500	STORM SEWER REMOVAL 12"	FOOT	40				40
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1				1
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1				1
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	6				6
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2				2
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1				1
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1				1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3				3
60500050	REMOVING CATCH BASINS	EACH	1				1
60500060	REMOVING INLETS	EACH	4				4
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3				3
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,530	1,530			
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	240	240			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				90% FED. 10% STATE		90% FED. 10% STATE	
ITEM NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	0021 SAFETY	0021 100% VILLAGE OF LAKE ZURICH	0031 LANDSCAPING	0040 STORM SEWERS
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	25	25			
* 72000200	SIGN PANEL - TYPE 2	SQ FT	44	44			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	13	13			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	218	218			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	463	463			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,209	1,209			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	114	114			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	42	42			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	42	42			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	721	721			
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	59	59			
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	205	205			
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	40	40			
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	426	426			
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	232	232			
* 81400100	HANDHOLE	EACH	4	4			
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4	4			
* 81400300	DOUBLE HANDHOLE	EACH	1	1			
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,025	1,025			
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2			
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	1			
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1	1			
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	787	787			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,435	812	623		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,041	2,041			
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	859	859			
* 87300805	ELECTRIC CABLE IN TRENCH, SERVICE, NO. 6 2 C	FOOT	35	35			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,474	1,474			
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2	2			
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2	2			
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1	1			
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1	1			
* 87702330	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 26 FT.	EACH	1	1			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	16			
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4			
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	40	40			
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2			
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8	8			
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1			
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1			
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2	2			
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1	1			
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4	4			
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10	10			
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	6	6			
* 88600100	DETECTOR LOOP, TYPE I	FOOT	587	587			

* DENOTES SPECIALTY ITEM