

80% FED.
20% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	62	62
40600300	AGGREGATE (PRIME COAT)	TON	488	488
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	18	18
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1,401	1,401
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,034	1,034
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	8,175	8,175
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	81,235	81,235
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,461	3,461
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	4,494	4,494
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	48	48
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	504	504
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	728	728
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	2,170	2,170
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	28	28
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	24,600	24,600
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	4,374	4,374
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43,628	43,628
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19,828	19,828
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4,104	4,104
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,044	2,044
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,764	3,764
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,640	1,640
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2,127	2,127
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24,356	24,356
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9,840	9,840
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3,012	3,012
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,086	1,086
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,882	1,882
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	183	183

* INDICATES SPECIALTY ITEM

80% FED.
20% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	48	48
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,820	1,820
Z0018500	DRAINAGE STRUCTURE TO BE CLEANED	EACH	104	104
Z0076600	TRAINEES	— HOUR —	— 500 —	— 500 —
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0030050	TEMPORARY INFORMATION SIGNING	SO FT	52	52
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	3,504	3,504
X5539700	STORM SEWERS TO BE CLEANED	FOOT	4,056	4,056
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	249	249
XX005972	STAMPED ASPHALT CROSSWALK	SO YD	498	498
Z0048900	RAILROAD TRACK REMOVAL	FOOT	125	125
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	67	67
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	596	596
42400800	DETECTABLE WARNINGS	SQ FT	108	108
44000100	PAVEMENT REMOVAL	SQ YD	684	684
44000600	SIDEWALK REMOVAL	SQ FT	596	596
60619121	CONCRETE MEDIAN, TYPE SB-6	SQ FT	684	684
* 72000100	SIGN PANEL - TYPE 1	SQ FT	92	92
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	22	22
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	11	11
* 72900100	METAL POST - TYPE A	FOOT	100	100
* 72900200	METAL POST - TYPE B	FOOT	40	40

* INDICATES SPECIALTY ITEM
Δ = Non-participating

Rev. 4-15-11

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 022-077-0001-0001-0001
 12/2010
 ...\\dotcom\p\B\2013\441
 12/2010
 12/2010



DESIGNED - CAC	REVISED - PER IDOT 2-3-11
DRAWN - BCD	REVISED -
CHECKED - RWL	REVISED -
DATE - 12-17-10	FILE - 100153-w13-soq.shp

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTH AVENUE
MILWAUKEE AVENUE TO CLARK STREET
SUMMARY OF QUANTITIES

F.A.P. RTE. 307	SECTION 2010-140-RS	COUNTY COOK	TOTAL SHEETS 29	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60N19	

SCALE: NONE

STA. TO STA.