

URBAN

CODE	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTR. TYPE CODE
				STRUCTURE 0040 STATE 100%
20100110	Tree Removal (6 to 15 Units Diameter)	Unit	39	39
20100210	Tree Removal (Over 15 Units Diameter)	Unit	16	16
20700220	Porous Granular Embankment	Cu. Yd.	81.2	81.2
28100107	Stone Riprap, Class A4	Sq. Yd.	39	39
28200200	Filter Fabric	Sq. Yd.	39	39
42001300	Protective Coat	Sq. Yd.	86	86
44201670	Class D Patches, Type 1, 2 Inch	Sq. Yd.	9	9
50200100	Structure Excavation	Cu. Yd.	6	6
50300225	Concrete Structures	Cu. Yd.	14	14
50500505	Stud Shear Connectors	Each	48	48
50800205	Reinforcement Bars, Epoxy Coated	Pound	1460	1460
59100100	Geocomposite Wall Drain	Sq. Yd.	615	615
* 63301210	Remove and Reerect Steel Plate Beam Guardrail, Type A	Foot	232	232
67000400	Engineer's Field Office, Type A	Cal. Mo.	6	6
67100100	Mobilization	L. Sum	1	1
70300240	Temporary Pavement Marking-Line 6"	Foot	168	168
70301000	Work Zone Pavement Marking Removal	Sq. Ft.	112	112
70400100	Temporary Concrete Barrier	Foot	168	168
70400200	Relocate Temporary Concrete Barrier	Foot	168	168
78200530	Barrier Wall Markers, Type C	Each	14	14
X5121800	Permanent Steel Sheet Piling	Sq. Ft.	2931	2931
X7011015	Traffic Control and Protection, (Expressways)	L. Sum	1	1
X7030030	Wet Reflective Temporary Tape Type III, 4 Inch	Foot	336	336
Z0030250	Impact Attenuators, Temporary (Non-Redirective), Test Level 3	Each	1	1
Z0030350	Impact Attenuators, Relocate (Non-Redirective), Test Level 3	Each	1	1
Z0030850	Temporary Information Signing	Sq. Ft.	41	41
Z0046304	Pipe Underdrains for Structures 4"	Foot	145	145

*Specialty Item

FILE #	FILE NAME =	USER NAME = #USER#	DESIGNED - AMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES STRUCTURE NO. 016-1211				F.A.P. RTE. 332	SECTION 0312-708W-1	COUNTY COOK	TOTAL SHEETS 17	SHEET NO. 3
	PLOT SCALE = #SCALE#	CHECKED - JMH	REVISED -	SCALE:		SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT						
	PLOT DATE = #DATE#	DATE - FEBRUARY, 2011	REVISED -	CONTRACT NO. 60N81										

Rev.