

PLAN SURVEYED BY DATE  
 PLOTTED BY CHECKED  
 NOTE BOOK NO. OF WAY CHECKED  
 NO. CADD FILE NAME

PROFILE SURVEYED BY DATE  
 PLOTTED BY CHECKED  
 NOTE BOOK NO. OF WAY CHECKED  
 NO. STRUCTURE NO. STATUS CHG

| SUMMARY OF QUANTITIES |    |                        |          |   |       |       |
|-----------------------|----|------------------------|----------|---|-------|-------|
| SP                    | SI | CONSTRUCTION TYPE CODE | CODE NO  | ITEM  | UNIT  | TOTAL |
| *                     |    | 0031                   | 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER)                     | UNIT  | 24    |
| *                     |    | 0031                   | 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER)                     | UNIT  | 30    |
|                       |    | 0031                   | 20101000 | TEMPORARY FENCE   | FOOT  | 997   |
| *                     |    | 0031                   | 20101200 | TREE ROOT PRUNING   | EACH  | 34    |
| *                     |    | 0031                   | 20101300 | TREE PRUNING (1 TO 10 INCH DIAMETER)                      | EACH  | 23    |
| *                     |    | 0031                   | 20101350 | TREE PRUNING (OVER 10 INCH DIAMETER)                      | EACH  | 12    |
| *                     |    | 0021                   | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL               | CU YD | 825   |
|                       |    | 0021                   | 20400800 | FURNISHED EXCAVATION                                      | CU YD | 1862  |
|                       |    | 0021                   | 20700220 | POROUS GRANULAR EMBANKMENT                                | CU YD | 108   |
|                       |    | 0021                   | 20800150 | TRENCH BACKFILL   | CU YD | 57    |
| *                     |    | 0031                   | 21101615 | TOPSOIL FURNISH AND PLACE, 4"                             | SQ YD | 5480  |
| *                     |    | 0031                   | 25000400 | NITROGEN FERTILIZER NUTRIENT                              | POUND | 85    |
| *                     |    | 0031                   | 25000600 | POTASSIUM FERTILIZER NUTRIENT                             | POUND | 85    |
| *                     |    | 0031                   | 25200110 | SODDING, SALT TOLERANT                                    | SQ YD | 5480  |
| *                     |    | 0031                   | 25200200 | SUPPLEMENTAL WATERING                                     | UNIT  | 55    |
|                       |    | 0043                   | 28100105 | STONE RIPRAP, CLASS A3                                    | SQ YD | 25    |
|                       |    | 0043                   | 28200200 | FILTER FABRIC   | SQ YD | 25    |
|                       |    | 0004                   | 35501308 | HOT-MIX ASPHALT BASE COURSE, 6"                           | SQ YD | 1091  |
|                       |    | 0004                   | 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT              | SQ YD | 20    |
|                       |    | 0004                   | 40801005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES                  | TON   | 0.2   |
|                       |    | 0004                   | 40803310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 50             | TON   | 119   |
|                       |    | 0004                   | 42300300 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH        | SQ YD | 344   |
|                       |    | 0021                   | 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH                  | SQ FT | 25735 |
|                       |    | 0021                   | 42400400 | PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH                  | SQ FT | 785   |
|                       |    | 0021                   | 42400800 | DETECTABLE WARNINGS                                       | SQ FT | 175   |
|                       |    | 0004                   | 44000100 | PAVEMENT REMOVAL  | SQ YD | 40    |
|                       |    | 0004                   | 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2"                       | SQ YD | 125   |
|                       |    | 0004                   | 44000200 | DRIVEWAY PAVEMENT REMOVAL                                 | SQ YD | 1781  |
| *                     |    | 0004                   | 44000500 | COMBINATION CURB & GUTTER REMOVAL                         | FOOT  | 27    |
|                       |    | 0021                   | 44000600 | SIDEWALK REMOVAL  | SQ FT | 40    |
|                       |    | 0004                   | 44201723 | CLASS D PATCHES, TYPE M, 6 INCH                           | SQ YD | 114   |
|                       |    | 0004                   | 50104400 | CONCRETE HEADWALL REMOVAL                                 | EACH  | 2     |
|                       |    | 0043                   | 50105220 | PIPE CULVERT REMOVAL                                      | FOOT  | 147   |
|                       |    | 0043                   | 54213447 | END SECTIONS 12"  | EACH  | 10    |
|                       |    | 0043                   | 54213450 | END SECTIONS 15"  | EACH  | 2     |
|                       |    | 0043                   | 54213453 | END SECTIONS 18"  | EACH  | 2     |
|                       |    | 0043                   | 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"       | EACH  | 7     |
|                       |    | 0043                   | 54213681 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"       | EACH  | 2     |
|                       |    | 0043                   | 542A0217 | PIPE CULVERTS, CLASS A, TYPE 1 12"                        | FOOT  | 318   |
|                       |    | 0043                   | 542A0241 | PIPE CULVERTS, CLASS A, TYPE 1 36"                        | FOOT  | 68    |
|                       |    | 0043                   | 542D0220 | PIPE CULVERTS, CLASS D, TYPE 1 15"                        | FOOT  | 29    |
|                       |    | 0043                   | 542D0223 | PIPE CULVERTS, CLASS D, TYPE 1 18"                        | FOOT  | 35    |
|                       |    | 0043                   | 550B0050 | STORM SEWERS, CLASS B, TYPE 1 12"                         | FOOT  | 156   |
|                       |    | 0043                   | 55100400 | STORM SEWER REMOVAL 10"                                   | FOOT  | 8     |
| *                     |    | 0043                   | 56500600 | DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED               | EACH  | 2     |
|                       |    | 0043                   | 60200105 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID | EACH  | 4     |
|                       |    | 0043                   | 60207305 | CATCH BASINS, TYPE C, TYPE 5 FRAME, OPEN LID              | EACH  | 2     |
|                       |    | 0004                   | 60803800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-5.12         | FOOT  | 27    |
|                       |    | 0021                   | 63200310 | GUARDRAIL REMOVAL   | FOOT  | 26    |
|                       |    | 0004                   | 67100100 | MOBILIZATION  | L SUM | 1     |
|                       |    | 0021                   | 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801           | L SUM | 1     |
| *                     |    | 0004                   | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6"                  | FOOT  | 280   |

| SUMMARY OF QUANTITIES |    |                        |          |   |       |       |
|-----------------------|----|------------------------|----------|---|-------|-------|
| SP                    | SI | CONSTRUCTION TYPE CODE | CODE NO  | ITEM  | UNIT  | TOTAL |
| *                     |    | 0031                   | B2000116 | TREE, ACER CAMPESTRE (HEDGE MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED                   | EACH  | 1     |
| *                     |    | 0031                   | B2000216 | TREE, ACER GINNALA (AMUR MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED                      | EACH  | 1     |
| *                     |    | 0031                   | B2000220 | TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED   | EACH  | 1     |
| *                     |    | 0031                   | B2010016 | TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH  | 1     |
| *                     |    | 0031                   | K0026830 | SHRUB REMOVAL   | EACH  | 9     |
| *                     |    | 0021                   | X0325793 | WOOD FENCE, TYPE 1  | FOOT  | 45    |
| *                     |    | 0043                   | X0976500 | END SECTIONS TO BE REMOVED  | EACH  | 2     |
| *                     |    | 0021                   | X002133  | RELOCATE SIGN AND BASE  | EACH  | 1     |
| *                     |    | 0004                   | Z0013796 | CONSTRUCTION LAYOUT   | L SUM | 1     |
| *                     |    | 0031                   | Z0023204 | SEDIMENT CONTROL, SILT FENCE  | FOOT  | 234   |

FILE NAME = USFR NAME = DESIGNED -- MB REVISION --  
 DRAWN -- MP REVISION --  
 PLOT SCALE = CHECKED -- AJB REVISION --  
 PLOT DATE = DATE -- 10/29/2008 REVISION --

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCALE:

F.A.U. SECTION COUNTY TOTAL SHEET NO.  
 RTE. 08-00098-00-SW DUPAGE 22 3  
 SIDEWALK PROJECT CONTRACT NO. 63132  
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT