

| CODE NO.   | ITEM  | UNIT   | TOTAL QUANTITY | CONSTRUCTION CODE                |                           |                            |                            |
|------------|---|--------|----------------|----------------------------------|---------------------------|----------------------------|----------------------------|
|            |   |        |                | IRVING PARK RD BIKE PATH         |                           |                            | HIGGINS RD BIKE PATH       |
|            |   |        |                | 80% FED<br>20% LOCAL             | 80% FED<br>20% LOCAL      | 80% FED<br>20% LOCAL       | 80% FED<br>20% LOCAL       |
|            |   |        |                | TRAFFIC SIGNALS<br>0021<br>URBAN | LIGHTING<br>0021<br>URBAN | BIKE PATH<br>0038<br>URBAN | BIKE PATH<br>0038<br>URBAN |
| 20100110   | TREE REMOVAL (6 TO 15 UNITS DIAMETER)                 | UNIT   | 250            |                                  |                           | 242                        | 8                          |
| 20100210   | TREE REMOVAL (OVER 15 UNITS DIAMETER)                 | UNIT   | 93             |                                  |                           | 93                         |                            |
| 20100500   | TREE REMOVAL, ACRES                                   | ACRE   | 0.25           |                                  |                           | 0.25                       |                            |
| 20101100   | TREE TRUNK PROTECTION                                 | EACH   | 21             |                                  |                           | 19                         | 2                          |
| 20200100   | EARTH EXCAVATION                                      | CU YD  | 430            |                                  |                           | 424                        | 6                          |
| 20201200   | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL           | CU YD  | 3,190          |                                  |                           | 2,718                      | 472                        |
| 20400800   | FURNISHED EXCAVATION                                  | CU YD  | 2,660          |                                  |                           | 1,563                      | 1,097                      |
| 20800150   | TRENCH BACKFILL                                       | CU YD  | 306            |                                  |                           | 248                        | 58                         |
| * 21101615 | TOPSOIL FURNISH AND PLACE, 4"                         | SQ YD  | 12,699         |                                  |                           | 10,801                     | 1,898                      |
| * 25000400 | NITROGEN FERTILIZER NUTRIENT                          | POUND  | 158            |                                  |                           | 134                        | 24                         |
| * 25000500 | PHOSPHORUS FERTILIZER NUTRIENT                        | POUND  | 158            |                                  |                           | 134                        | 24                         |
| * 25000600 | POTASSIUM FERTILIZER NUTRIENT                         | POUND  | 158            |                                  |                           | 134                        | 24                         |
| * 25200110 | SODDING, SALT TOLERANT                                | SQ YD  | 12,699         |                                  |                           | 10,801                     | 1,898                      |
| * 25200200 | SUPPLEMENTAL WATERING                                 | UNIT   | 648            |                                  |                           | 551                        | 97                         |
| 28000400   | PERIMETER EROSION BARRIER                             | FOOT   | 4,316          |                                  |                           | 3,805                      | 511                        |
| 28000510   | INLET FILTERS   | EACH   | 48             |                                  |                           | 41                         | 7                          |
| 31101400   | SUBBASE GRANULAR MATERIAL, TYPE B 6"                  | SQ YD  | 4,750          |                                  |                           | 4,307                      | 443                        |
| 35501308   | HOT-MIX ASPHALT BASE COURSE, 6"                       | SQ YD  | 49             |                                  |                           | 49                         |                            |
| 40600100   | BITUMINOUS MATERIALS (PRIME COAT)                     | GALLON | 2,376          |                                  |                           | 2,154                      | 222                        |
| 40603310   | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50          | TON    | 804            |                                  |                           | 730                        | 74                         |
| 42001300   | PROTECTIVE COAT                                       | SQ YD  | 160            |                                  |                           | 160                        |                            |
| 42400200   | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH              | SQ FT  | 112            |                                  |                           | 112                        |                            |
| 42400800   | DETECTABLE WARNINGS                                   | SQ FT  | 288            |                                  |                           | 272                        | 16                         |
| 44000100   | PAVEMENT REMOVAL                                      | SQ YD  | 503            |                                  |                           | 503                        |                            |
| 44000200   | DRIVEWAY PAVEMENT REMOVAL                             | SQ YD  | 78             |                                  |                           | 78                         |                            |
| 44000500   | COMBINATION CURB AND GUTTER REMOVAL                   | FOOT   | 500            |                                  |                           | 486                        | 14                         |
| 44000600   | SIDEWALK REMOVAL                                      | SQ FT  | 807            |                                  |                           | 807                        |                            |
| 44003100   | MEDIAN REMOVAL  | SQ FT  | 96             |                                  |                           | 96                         |                            |
| 44201765   | CLASS D PATCHES, TYPE II, 10 INCH                     | SQ YD  | 27             |                                  |                           | 27                         |                            |
| 50105220   | PIPE CULVERT REMOVAL                                  | FOOT   | 63             |                                  |                           | 63                         |                            |
| 54213669   | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"   | EACH   | 2              |                                  |                           | 1                          | 1                          |
| 54216185   | REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER | EACH   | 1              |                                  |                           | 1                          |                            |

\* SPECIALTY ITEMS

|             |                       |                   |           |   |   |                          |      |           |                    |        |              |           |
|-------------|-----------------------|-------------------|-----------|---|---|--------------------------|------|-----------|--------------------|--------|--------------|-----------|
| FILE NAME = | USER NAME = #USER#    | DESIGNED - LP     | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>IRVING PARK ROAD &amp; HIGGINS ROAD BIKE PATHS<br/>SUMMARY OF QUANTITIES</b> |                          |      | F.A. RTE. | SECTION            | COUNTY | TOTAL SHEETS | SHEET NO. |
| *FILE#      | PLOT SCALE = #SCALE#  | DRAWN - LP        | REVISED - |   |   |                          |      |           | 07-00091-00-BT     | COOK   | 70           | 3         |
|             | PLOT DATE = 11/3/2010 | CHECKED - JP      | REVISED - |   | SCALE: NONE   | SHEET NO. 3 OF 70 SHEETS | STA. | TO STA.   | CONTRACT NO. 63355 |        |              |           |
|             |                       | DATE - 10/26/2010 | REVISED - |   | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT                                 |                          |      |           |                    |        |              |           |