

TREE REMOVAL (6-15 UNITS)			
NO.	STATION	OFFSET (FT)	QUANTITY (UNIT)
1	126+69.78	29.8 RT	10.0
2	126+76.32	30.19 RT	10.0
3	126+76.32	30.19 RT	10.0
4	126+76.32	30.19 RT	10.0
5	126+76.32	30.19 RT	10.0
6	126+76.32	30.19 RT	10.0
7	126+76.32	30.19 RT	10.0
8	126+96.97	28.21 RT	12.0
9	127+00.00	30.08 RT	12.0
10	127+13.81	30.24 RT	12.0
11	127+13.81	30.24 RT	12.0
12	127+13.81	30.24 RT	12.0
13	127+34.35	30.08 RT	14.0
14	127+34.35	30.08 RT	14.0
15	127+34.35	30.08 RT	14.0
16	127+34.35	30.08 RT	14.0
17	127+47.12	29.51 RT	10.0
18	129+63.67	23 LT	10.0
TOTAL			206

TREE REMOVAL (OVER 15 UNITS)			
NO.	STATION	OFFSET (FT)	QUANTITY (UNIT)
1	126+48.33	28.73 RT	16.0
2	127+02.45	24.37 RT	42.0
3	127+22.61	28.77 RT	16.0
4	127+22.61	28.77 RT	16.0
5	129+62.90	25.49 RT	60.0
6	136+20.62	33 RT	28.0
7	136+54.29	26.69 LT	24.0
8	136+79.50	26.47 LT	30.0
TOTAL			232

STORM SEWER REMOVAL			
LOCATION STATION-STATION	10" (FT)	12" (FT)	
EAST CRYSTAL LAKE AVE			
125+10 - 128+00	85	-	
128+00 - 134+00	177	82	
134+00 - 137+17	-	-	
TOTAL		290	82

SIDEWALK REMOVAL			
NO.	LOCATION STA. - STA.	OFFSET	QUANTITY (SQ. FT)
EAST CRYSTAL LAKE AVE			
1	125+10 - 128+00	LT	999
2	125+10 - 128+00	RT	0.0
3	128+00 - 134+00	LT	2572
4	128+00 - 134+00	RT	94
5	134+00 - 137+17	LT	1350
6	134+00 - 137+17	RT	535
TOTAL			5550

NOTE: PERSONAL SIDEWALKS WILL BE REMOVED UP TO THE R.O.W. THESE QUANTITIES ARE INCLUDED IN THE ABOVE SCHEDULE.

HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT			
LOCATION STA. - STA.	OFFSET	QUANTITY (SQ. YD)	
EAST CRYSTAL LAKE AVE			
125+10	CL	55.56	
EAST STREET	LT	102	
MORGAN STREET	LT	54.5	
137+17	CL	48.9	
TOTAL			261

PAVEMENT REMOVAL		
LOCATION STA. - STA.	QUANTITY (SQ. YD)	
EAST CRYSTAL LAKE AVE		
125+10 - 128+00	157.5	
128+00 - 134+00	328.09	
134+00 - 137+17	170.6	
TEMPORARY PAVEMENT	51.3	
TOTAL		725

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH		
LOCATION STA. - STA.	QUANTITY (SQ. YD)	
EAST CRYSTAL LAKE AVE		
125+10 - 128+00	764.88	
128+00 - 134+00	1593.5	
134+00 - 137+17	868.62	
TOTAL		3200

DRIVEWAY PAVEMENT REMOVAL			
NO.	STATION	OFFSET	QUANTITY (SQ. YD)
1	125+81.35	CE RT	118.73
2	127+32.22	LT	15.79
3	127+88.96	LT	16.10
4	127+93.03	RT	52.88
5	128+0.952	LT	13.71
6	128+71.79	LT	11.83
7	129+34.65	RT	19.64
8	129+38.3	LT	15.12
9	130+1.8	LT	14.11
10	130+03.59	RT	15.70
11	131+13.39	LT	16.09
12	131+46.37	RT	110.29
13	131+13.39	LT	59.66
14	132+38.76	RT	35.12
15	132+95.8	RT	59.66
16	133+65.15	LT	40.59
17	133+85.9	RT	25.17
18	134+42.22	LT	26.92
19	134+61.24	LT	23.83
20	134+41.14	CE RT	68.59
21	134+79.11	RT	46.63
22	135+98.47 & 136+38.25	RT	125.16
23	136.05.01	LT	25.76
24	136+94.56	LT	22.53
TOTAL			990

LOCATION	EARTHWORK QUANTITIES																	
	EARTH EX. (CU YD)			ADJ. EARTH EX. (15%)			EMBANKMENT (CU YD)			BALANCE WASTE (+) OR SHORTAGE (-)			UNSUITABLE (CU YD)					
	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3	STAGE 1	STAGE 2	STAGE 3
EAST CRYSTAL LAKE AVENUE	300	290	60	345	335	69	254	188	0	92.3	145.7	69	210	220	0			
TOTAL		650		747.5			442			307			430					

NOTE: BASIS OF MEASUREMENT AND PAYMENT PER STANDARD SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, AND RECURRING SPECIAL PROVISIONS UNLESS MARKED IN THE MARGIN WITH "SPL" WHICH IDENTIFIES THOSE ITEMS WHICH ARE RULED BY SECTIONS OF THE CONTRACT SPECIAL PROVISIONS.