

SPECIALTY ITEM	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES										NON-PARTICIPATING WORK	
	ITEM #	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	STP ROADWAY 0003	STP HIGHWAY LIGHTING 0021	STP ORCHARD RD. @AUCUTT RD 0021	STP ORCHARD RD. @ ROCHESTER DR 0021	STP US ROUTE 30 0021	CMAQ SIGNAL SYSTEM 0021	STP LANDSCAPING 0031	ITEP BIKE PATH 0028	TRAINEES 0042			
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	699	699											
	550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	435	435											
	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	217	217											
	550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	30	30											
	550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	32	32											
	550A2550	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 21"	FOOT	101	101											
	550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	120	120											
	550A2570	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 27"	FOOT	13	13											
*	56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	11												11
	60109510	PIPE UNDERDRAINS, 4"	FOOT	1,832	1,832											
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	21	21											
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	35	35											
	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2											
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11											
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	19	19											
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	25	25											
	60255500	MANHOLES TO BE ADJUSTED	EACH	20	20											
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	8												8
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	18.4	18.4											
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	698	698											
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	20,830	20,830											
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	122	122											
	60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	8,812	8,812											
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	15											
	67100100	MOBILIZATION	L SUM	1	1											
	70106800	CHANGEABLE MESSAGE SIGNS	CAL MO	36	36											
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,350	1,350											
	70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	73	73											
	70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	23,148	23,148											
	70300240	TEMPORARY PAVEMENT MARKING LINE 6"	FOOT	418	418											
	70300260	TEMPORARY PAVEMENT MARKING LINE 12"	FOOT	379	379											
	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	400	400											
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	58,971	58,971											
	70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	2,887	2,887											
	70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	497	497											
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,171	14,171											
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,475	1,475											
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,475	1,475											
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	271	271											
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1												1
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1												1
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	7,951				791	551	6,609						
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	377				200	56	109						12
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	80				38	42							