

SPECIALTY ITEM	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODES									NON-PARTICIPATING WORK
	ITEM #	ITEM DESCRIPTION	FOOT UNIT	TOTAL QUANTITY	STP ROADWAY 0003	STP HIGHWAY LIGHTING 0021	STP ORCHARD RD. @AUCUTT RD 0021	STP ORCHARD RD. @ ROCHESTER DR 0021	STP US ROUTE 30 0021	CMAQ SIGNAL SYSTEM 0021	STP LANDSCAPING 0031	ITEP BIKE PATH 0028	TRAINEEES 0042	
*	81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	18			18							
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	217			168	43				6		
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	272			103	118		51				
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	824		194	409	221						
*	81400100	HANDHOLE	EACH	20			5	3		11		1		
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4			2	2						
*	81400300	DOUBLE HANDHOLE	EACH	2			1	1						
*	81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA., 1/64" POLYETHYLENE	FOOT	4,450		4,450								
*	81702160	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 1/0	FOOT	1,350		220	480	650						
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	8,702		190	1,110	793		6,609				
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	28		28								
*	83008400	LIGHT POLE, ALUMINUM, 40 FT. M.H., 10 FT. MAST ARM	EACH	24		24								
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	220		220								
*	8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	20		20								
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	24		24								
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4			1	1	1	1				
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3			1	1		1				
*	86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	2			1	1						
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	841								841		
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,126			811	466				849		
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5,004			1,250	3,754						
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,758			2,488	270						
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	8,588			2,940	3,504	2,144					
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	195			195							
*	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1								1		
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5			2	3						
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1				1						
*	87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1				1						
*	87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1			1							
*	87703040	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 62 FT.	EACH	1				1						
*	87703070	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 66 FT.	EACH	1			1							
*	87703080	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 68 FT.	EACH	1				1						
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24			8	12				4		
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8			4	4						
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	39				39						
*	87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	93			68	25						
*	87900200	DRILL EXISTING HANDHOLE	EACH	1						1				
*	87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	8						8				
*	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	9			3	6						
*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	17			7	10						
*	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3			2	1						
*	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3			2	1						
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4								4		
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	32			14	18						