

PAVEMENT MARKING SCHEDULE						
LOCATION	URETHANE PAVEMENT MARKING, LETTERS AND SYMBOLS	URETHANE PAVEMENT MARKING, LINE 4"	URETHANE PAVEMENT MARKING, LINE 6"	URETHANE PAVEMENT MARKING, LINE 12"	URETHANE PAVEMENT MARKING, LINE 24"	RECESSED REFLECTIVE PAVEMENT MARKER
	SQ FT	FOOT	FOOT	FOOT	FOOT	EACH
ORCHARD ROAD						
US ROUTE 30 to COUNTRYSIDE AVE.	109.2	8,381	603	105	0	88
COUNTRYSIDE AVE. to AUCUTT RD.	182.0	3,875	984	92	36	47
AUCUTT RD. to KNELL RD.	109.2	8,469	565	419	36	59
KNELL RD. to ROCHESTER DR.	291.2	5,856	1,533	334	48	64
ROCHESTER DR. to CORNELL AVE.	72.8	5,081	566	338	36	41
NORTH OF JERICHO RD.	0.0	270	217	0	0	19
AUCUTT ROAD (STA. 71+26 TO 76+69)	145.6	2,948	253	0	33	0
KNELL ROAD (STA. 51+20 TO 52+28)	72.8	1,650	192	0	0	0
ROCHESTER DRIVE (STA. 31+20 TO 32+50)	0.0	978	0	0	26	0
JERICHO PATH EXTENSION	0.0	0	920	366	0	0
TOTALS	982.8	37,508	5,833	1,654	215	318

SIGN REMOVAL		
STATION	OFFSET	REMOVE SIGN PANEL ASSEMBLY-TYPE A
		EACH
ORCHARD RD.		
103+60.00	63.00 RT	1
104+08.00	52.00 RT	1
105+43.00	35.00 RT	1
110+40.49	13.78 LT	1
114+85.43	42.87 RT	1
115+84.86	64.92 RT	1
117+23.89	9.96 LT	1
120+42.82	66.72 RT	1
120+86.67	66.15 RT	1
122+34.57	48.14 RT	1
124+74.06	12.99 LT	1
126+08.38	12.27 LT	1
128+53.42	49.91 RT	1
132+69.17	14.67 LT	1
138+44.44	11.94 LT	1
145+13.23	44.75 RT	1
146+63.98	60.58 RT	1
152+19.83	44.18 RT	1
152+26.20	12.11 LT	1
154+45.71	10.56 LT	1
156+22.35	12.75 LT	1
156+74.66	9.05 LT	1
157+77.83	41.67 RT	1
161+35.08	13.38 LT	1
163+88.33	11.53 LT	1
164+28.67	16.18 LT	1
173+55.00	50.00 LT	1
AUCUTT RD.		
70+66.35	31.50 LT	1
71+87.52	28.78 LT	1
72+58.57	21.53 RT	1
76+24.73	25.09 RT	1
76+25.19	21.19 LT	1
76+41.88	21.08 LT	1
76+42.05	24.81 RT	1
KNELL RD.		
50+86.07	28.14 LT	1
51+18.80	25.47 RT	1
ROCHESTER DR.		
30+62.12	22.95 LT	1
31+04.31	20.01 RT	1
TOTAL		38

PAVEMENT REMOVAL SCHEDULE			
LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL, 2 1/4"	PAVEMENT REMOVAL
	SQ YD	SQ YD	SQ YD
STAGE II			
ORCHARD ROAD			
104+89.01 TO 114+92.36			953
163+71.60 TO 171+62.62			130
STAGE III			
ORCHARD ROAD			
104+89.01 TO 114+92.36			4,615
114+92.36 TO 127+67.00			4,941
127+67.00 TO 130+00.00			2,042
134+00.00 TO 139+00.00			1,552
144+00.00 TO 147+06.60			1,598
147+06.60 TO 163+71.60			7,731
163+71.60 TO 171+62.62			4,198
AUCUTT ROAD			
71+26.17 TO 76+64.46		1778	111
76+64.46 TO 76+68.96	13		
KNELL ROAD			
51+20.45 TO 52+23.00		409	
52+23.00 TO 52+27.50	18		
ROCHESTER DRIVE			
31+19.96 TO 32+45.50		363	91
32+45.50 TO 32+50.00	13		331
STAGE IV			
ORCHARD ROAD			
171+62.60 TO 175+20.00			601
TOTAL	44	2,550	28,894

DRIVEWAY REMOVAL SCHEDULE		
LOCATION	SIDE	DRIVEWAY PAVEMENT REMOVAL
		SQ YD
ORCHARD RD.		
120+63.57	RT	303
154+88.65	RT	335
157+59.98	LT	103
159+07.40	RT	174
161+18.61	LT	279
164+04.00	LT	215
AUCUTT RD.		
73+60.70	RT	362
ROCHESTER DR.		
31+81.88	LT	146
TOTAL		1,918

DRIVEWAY PAVEMENT SCHEDULE						
LOCATION	SIDE	TYPE	AGGREGATE BASE COURSE, TYPE B, 8"	HMA BASE COURSE, 6"	HMA BASE COURSE, 8"	HMA SURFACE COURSE, MIX "C", N50
			SQ YD	SQ YD	SQ YD	TON
ORCHARD RD.						
116+00.00	LT	FE	70			8
121+84.37	RT	CE			225	25
152+52.10	RT	CE			58	7
152+54.58	LT	PE		69		8
157+59.98	LT	FE	42			5
159+08.40	RT	CE			102	11
159+23.76	LT	FE	43			5
161+14.11	LT	CE			153	17
164+04.00	LT	PE		77		9
AUCUTT RD.						
73+60.70	RT	CE			204	23
TOTAL			155	146	742	117