






LEGEND

-  EROSION CONTROL BLANKET
-  TEMPORARY DITCH CHECK
-  INLET AND PIPE PROTECTION
-  TEMPORARY FENCE
-  PERIMETER EROSION BARRIER

NOTES:

- 1: FOR EROSION AND SEDIMENT CONTROL MEASURES AT STORMWATER BASINS SEE BASIN GRADING SHEETS
- 2: COORDINATE THE WORK ON THIS SHEET WITH THE LANDSCAPING PLANS
- 3: ALL SEEDED SURFACES SHALL BE COVERED WITH AN APPROVED EROSION CONTROL BLANKET WITHIN 7 CALENDAR DAYS OF FINAL GRADING
- 4: DURING WORK ON THE BANK OF JERICHO LAKE, WORK MUST BE TIMED TO TAKE PLACE DURING LOW OR NO-FLOW CONDITIONS. EQUIPMENT SHALL WORK FROM THE BANK IF POSSIBLE AND THIS AREA SHOULD BE IMMEDIATELY BROUGHT TO FINAL GRADE, SEEDED, AND STABILIZED UPON COMPLETION OF THE GRADING WORK.