SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 DIAMETER UNITS)

UNIT		LOCATION			REMARK'S
8	STA.	68 + 79	45.1'	RT	
8	STA.	68 + 80	49.1'	RT	
8	STA.	68 + 86	67'	LT	
8	STA.	69 + 5	44.1'	RT	
6	STA.	69 + 22	46'	LT	
10	STA.	69 + 36	61.5'	LT	
48	TOTAL				

20100210 TREE REMOVAL (OVER 15 DIAMETER UNITS)

UNIT		LOCATION			REMARK'S
16	STA.	68 + 71	76.6'	RT	
18	STA.	69 + 5	57.5'	RT	
20	STA.	69 + 12	48.7'	RT	
54	TOTAL				

20200100 EARTH EXCAVATION

CU YD		LOCATION			REMARK'S
110	LT & RT STA.	68 + 31	TO	70 + 0	
110	TOTAL				

20200200 ROCK EXCAVATION

CU YD		LOCATION	REMARK'S
20	LT & RT STA.	69 + 0	Possible excavation under proposed Box Culvert
20	TOTAL		

25100630 EROSION CONTROL BLANKET

SQ YD		LOCATION			REMARK'S
438.0	LT. STA.	68 + 75	TO	70 + 0	
438.0	TOTAL				

25200110 SODDING, SALT TOLERANT

SQ YD		LOCATION			REMARK'S
278.0	RT. STA.	67 + 77	TO	69 + 27	
278.0	TOTAL				

25200200 SUPPLEMENTAL WATERING

UNIT		LOCATION			REMARK'S
13.0	LT. STA.	67 + 77	TO	69 + 27	
13.0	TOTAL				

28000305 TEMPORARY DITCH CHECKS

FOOT		LOCATION	REMARK'S
20	LT. STA	69 + 50	
20	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT		LOCATION			REMARK'S
145	RT STA.	69 + 58	TO	69 + 28	
26	LT STA.	68 + 77	TO	69 + 3	
171	TOTAL				

28000500 INLET AND PIPE PROTECTION

EACH		LOCATION	REMARK'S
1	LT. STA.	69 + 0	
1	TOTAL		

28100107 STONE RIPRAP, CLASS A4

SQ YD		LOCATION	REMARK'S
68.0	LT. STA.	69 + 0	
79.0	RT. STA.	69 + 0	
147.0	TOTAL		

28200200 FILTER FABRIC

SQ YD		LOCATION	REMARK'S
470.0	LT & RT STA	69 + 0	
470.0	TOTAL		

40603335 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50

TON		LOCATION			REMARK'S
71.0	LT & RT STA	68 + 31	TO	69 + 27	
71.0	TOTAL				

42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7"

SQ YD		LOCATION	REMARK'S
56.0	RT STA.	68 + 50	
56.0	TOTAL		

44000158 HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"

SQ YD		LOCATION			REMARK'S
214.0	LT & RT STA	68 + 31	TO	68 + 74	Includes shoulder and 2nd Ave.
214.0	TOTAL				

44000400 GUTTER REMOVAL

FOOT		LOCATION			REMARK'S
29	RT STA.	68 + 31	TO	68 + 60	
20	RT STA.	69 + 6	TO	69 + 26	
49	TOTAL				

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

SQ YD		LOCATION			REMARK'S
155.0	CL STA.	68 + 74	TO	69 + 27	
155.0	TOTAL				

48101200 AGGREGATE SHOULDERS, TYPE B

TON		LOCATION			REMARK'S
32.0	LT STA.	68 + 31	TO	70 + 0	
32.0	TOTAL				

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

EACH		LOCATION	REMARK'S
1	STA.	69 + 0	12x6 Concrete Box Culvert
1	TOTAL		

51500100 NAME PLATES

EACH		LOCATION	REMARK'S
1		69 + 0	SN 081-1129
1	TOTAL		

54010805 PRECAST CONCRETE BOX CULVERTS 8' X 5'

FOOT		LOCATION	REMARK'S
146		69 + 0	
146	TOTAL		

60600095 CLASS SI CONCRETE OULET

CU YD		LOCATION	REMARK'S
2	RT. STA.	68 + 95	OUTLET OVER CULVERT
2	TOTAL		

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

FOOT		LOCATION			REMARK'S
88	RT. STA.	68 + 31	TO	69 + 27	
88	TOTAL				