



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 19, 2011

SUBJECT: FAI Route 57
Project ACIM-057-6 (190) 306
Section (46-2)I, HBR, VBR
Kankakee County
Contract No. 66409
Item No. 149, April 29, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iv of the Table of Contents to the Special Provisions.
3. Added pages 194 - 195 to the Special Provisions.
4. Revised sheets 1, 2, 6, 8, 13, 28, 60 - 62, 211, 273, 306 & 329 of the Plans.
5. Added sheet 225A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read 'Ted B. Walschleger', followed by a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Eric Therkildsen, Region 2, District 3; Mike Renner; D. Carl Puzey;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0325938	TEMP WIR INTERCON COM	L SUM	1.000				
X0326208	ALTERNATE RTE SIGNING	L SUM	1.000				
X0326867	RADAR SPEED TRAILER	CAL MO	35.000				
X0326880	MESSAGE BOARD VEH DRV	HOUR	600.000				
X0326907	PORT VHMNT CH MSS SGN	CAL MO	35.000				
X0327131	DRAIN STRUCTURES N1	EACH	1.000				
X0327132	DRAIN STRUCTURES N2	EACH	1.000				
X0327133	SOIL NAIL WALL	SQ FT	1,505.000				
X0703200	CONCRETE ISLAND SPL	SQ FT	1,100.000				
X2020502	BRACED EXCAVATION	CU YD	4,214.000				
X2070304	POROUS GRAN EMB SPEC	CU YD	730.000				
X2130010	EXPLOR TRENCH SPL	FOOT	250.000				
X4211070	WF BM TERM JT COM VAR	EACH	2.000				
X4401198	HMA SURF REM VAR DP	SQ YD	6,712.000				
X6013600	PIPE UNDERDRAIN 4 MOD	FOOT	43,381.900				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7010240	TR CONT SURVEILL SPL	CAL DA	540.000				
X7010805	TR C-PROT 701401 SPL	L SUM	1.000				
X7030030	WET REF TEM TAPE T3 4	FOOT	140,966.000				
X7030040	WET REF TEM TAPE T3 6	FOOT	11,800.000				
X7030055	WET REF TEM TPE T3 24	FOOT	492.000				
X7800610	URETH PAVT MK LINE 4	FOOT	69,932.000				
X7800640	URETH PAVT MK LINE 8	FOOT	10,424.000				
X7800650	URETH PAVT MK LINE 12	FOOT	3,760.000				
X7800680	URETH PAVT MK LINE 24	FOOT	330.000				
X7830070	GRV RCSD PVT MRKG 5	FOOT	43,782.000				
X7830076	GRV RCSD PVT MRKG 9	FOOT	3,102.000				
X8050010	SERV INSTALL GRND MT	EACH	1.000				
X8050015	SERV INSTALL POLE MT	EACH	1.000				
X8410118	MAINT TEMP LIGHT SYS	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8730320	EC C SIGL 20 3C TW SH	FOOT	2,118.000				
Z0001050	AGG SUBGRADE 12	SQ YD	110,580.000				
Z0001058	AGG SUBGRADE 18	SQ YD	1,066.000				
Z0001060	AGG SUBGRADE 24	SQ YD	1,979.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018002	DRAINAGE SCUPPR DS-11	EACH	4.000				
Z0018800	DRAINAGE SYSTEM	L SUM	1.000				
Z0022800	FENCE REMOVAL	FOOT	16,148.000				
Z0026407	TEMP SHT PILING	SQ FT	5,722.000				
Z0029999	IMPACT ATTENUATOR REM	EACH	9.000				
Z0030030	IMP ATTEN FRD NAR TL3	EACH	2.000				
* Z0030040	IMP ATTEN FRD WID TL2	EACH	6.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	4.000				
Z0030270	IMP ATTN TEMP FRW TL3	EACH	5.000				
Z0030330	IMP ATTN REL FRD TL3	EACH	13.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030850	TEMP INFO SIGNING	SQ FT	51.400				
Z0033056	OPTIM TRAF SIGNAL SYS	EACH	1.000				
Z0034105	MATL TRANSFER DEVICE	TON	7,438.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	655.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0062456	TEMP PAVEMENT	SQ YD	30,332.000				
Z0065704	BIT CT AG SLOPEWALL 6	SQ YD	2,109.000				
Z0065740	SLOT DR 12" W/VAR SL	FOOT	2,490.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				
Z0076600	TRAINEES	HOUR	5,000.000		0.800		4,000.000
20100110	TREE REMOV 6-15	UNIT	1,662.000				
20100210	TREE REMOV OVER 15	UNIT	3,461.000				
20101000	TEMPORARY FENCE	FOOT	1,516.000				
20101100	TREE TRUNK PROTECTION	EACH	20.000				
20200100	EARTH EXCAVATION	CU YD	248,559.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
20201200	REM & DISP UNS MATL	CU YD	26,978.000				
20400800	FURNISHED EXCAVATION	CU YD	27,045.000				
20800150	TRENCH BACKFILL	CU YD	3,639.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	3,044.000				
21101505	TOPSOIL EXC & PLAC	CU YD	26,530.000				
25000210	SEEDING CL 2A	ACRE	31.100				
25000312	SEEDING CL 4A	ACRE	18.200				
25000400	NITROGEN FERT NUTR	POUND	2,973.000				
25000500	PHOSPHORUS FERT NUTR	POUND	2,973.000				
25000600	POTASSIUM FERT NUTR	POUND	2,973.000				
25100115	MULCH METHOD 2	ACRE	70.400				
25100630	EROSION CONTR BLANKET	SQ YD	150,524.000				
25200110	SODDING SALT TOLERANT	SQ YD	14,006.000				
25200200	SUPPLE WATERING	UNIT	666.000				
28000200	EARTH EXC - EROS CONT	CU YD	1,420.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000250	TEMP EROS CONTR SEED	POUND	5,220.000				
28000305	TEMP DITCH CHECKS	FOOT	4,100.000				
28000400	PERIMETER EROS BAR	FOOT	4,636.000				
28000500	INLET & PIPE PROTECT	EACH	5.000				
28000510	INLET FILTERS	EACH	109.000				
28100107	STONE RIPRAP CL A4	SQ YD	120.000				
28100707	STONE DUMP RIP CL A4	SQ YD	100.000				
28200200	FILTER FABRIC	SQ YD	190.000				
31100500	SUB GRAN MAT A 6	SQ YD	3,992.000				
31100910	SUB GRAN MAT A 12	SQ YD	33,933.000				
31102000	SUB GRAN MAT C	CU YD	2,296.000				
31200500	STAB SUBBASE HMA 4	SQ YD	97,667.000				
35300500	PCC BSE CSE 10	SQ YD	10,454.000				
40600100	BIT MATLS PR CT	GALLON	42,032.000				
40600115	P BIT MATLS PR CT	GALLON	12,228.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600300	AGG PR CT	TON	5.000				
40600845	P LEV BIND MM N90	TON	257.000				
40600895	CONSTRUC TEST STRIP	EACH	6.000				
40603090	HMA BC IL-19.0 N90	TON	7,040.000				
40603240	P HMA BC IL19.0 N90	TON	5,239.000				
40603345	HMA SC "D" N90	TON	1,012.000				
40603545	P HMA SC "D" N90	TON	5,864.000				
40603570	P HMA SC "E" N90	TON	2,199.000				
40701841	HMA PAVT FD 8	SQ YD	2,454.000				
40800050	INCIDENTAL HMA SURF	TON	304.000				
42000501	PCC PVT 10 JOINTED	SQ YD	42,331.000				
42001200	PAVEMENT FABRIC	SQ YD	42,331.000				
42001300	PROTECTIVE COAT	SQ YD	139,215.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	2,726.000				
42100345	CONT R PCC PVT 12 1/4	SQ YD	52,712.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42100615	PAVT REINFORCEMENT	SQ YD	52,712.000				
42101030	WF BM TERM JT COMP 36	EACH	2.000				
42101100	TRANS TERM JT COMP 36	EACH	4.000				
42400200	PC CONC SIDEWALK 5	SQ FT	332.000				
42400800	DETECTABLE WARNINGS	SQ FT	80.000				
44000100	PAVEMENT REM	SQ YD	80,387.000				
44000157	HMA SURF REM 2	SQ YD	31,165.000				
44000159	HMA SURF REM 2 1/2	SQ YD	5,832.000				
44000200	DRIVE PAVEMENT REM	SQ YD	141.000				
44000500	COMB CURB GUTTER REM	FOOT	6,541.000				
44003100	MEDIAN REMOVAL	SQ FT	35,148.000				
44004000	PAVED DITCH REMOVAL	FOOT	1,144.100				
44004250	PAVED SHLD REMOVAL	SQ YD	62,660.000				
44201803	CL D PATCH T2 13	SQ YD	81.000				
44201807	CL D PATCH T3 13	SQ YD	22.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201809	CL D PATCH T4 13	SQ YD	125.000				
44201851	CL D PATCH T2 17	SQ YD	38.000				
44201855	CL D PATCH T3 17	SQ YD	32.000				
44201857	CL D PATCH T4 17	SQ YD	27.000				
44300200	STRIP REF CR CON TR	FOOT	950.000				
48101200	AGGREGATE SHLDS B	TON	4,667.000				
48300500	PCC SHOULDERS 10	SQ YD	5,993.000				
48300705	PCC SHOULDERS 12 1/4	SQ YD	19,391.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50100500	REM EXIST STRUCT N3	EACH	1.000				
50100600	REM EXIST STRUCT N4	EACH	1.000				
50102400	CONC REM	CU YD	16.900				
50104650	SLOPE WALL REMOV	SQ YD	149.000				
50105220	PIPE CULVERT REMOV	FOOT	129.300				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50157300	PROTECTIVE SHIELD	SQ YD	3,925.000				
* 50200100	STRUCTURE EXCAVATION	CU YD	1,285.000				
* 50300225	CONC STRUCT	CU YD	2,291.600				
50300255	CONC SUP-STR	CU YD	2,723.000				
50300260	BR DECK GROOVING	SQ YD	7,089.000				
50300280	CONCRETE ENCASEMENT	CU YD	35.000				
50300300	PROTECTIVE COAT	SQ YD	8,059.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	34,896.000				
* 50800205	REINF BARS, EPOXY CTD	POUND	1,006,838.000				
50800515	BAR SPLICERS	EACH	4,647.000				
51100100	SLOPE WALL 4	SQ YD	1,322.000				
51201500	FUR STL PILE HP10X57	FOOT	3,916.000				
51202305	DRIVING PILES	FOOT	3,916.000				
51203500	TEST PILE ST HP10X57	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51204650	PILE SHOES	EACH	98.000				
51500100	NAME PLATES	EACH	4.000				
52100010	ELAST BEARING ASSY T1	EACH	80.000				
52100510	ANCHOR BOLTS 3/4	EACH	36.000				
52100520	ANCHOR BOLTS 1	EACH	320.000				
54001001	BOX CUL END SEC C1	EACH	1.000				
54001002	BOX CUL END SEC C2	EACH	1.000				
54001007	BOX CUL END SEC C7	EACH	1.000				
54002050	EXPAN BOLTS 3/4 X 9	EACH	24.000				
54010302	PCBC 3X2	FOOT	34.800				
54010602	PCBC 6X2	FOOT	84.900				
542A0229	P CUL CL A 1 24	FOOT	497.800				
542A1081	P CUL CL A 2 36	FOOT	60.800				
542A1921	P CUL CL A 3 36	FOOT	330.900				
542A8215	P CUL CL A 2 EQRS 30	FOOT	128.500				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A8221	P CUL CL A 2 EQRS 36	FOOT	184.000				
54213657	PRC FLAR END SEC 12	EACH	13.000				
54213660	PRC FLAR END SEC 15	EACH	5.000				
54213663	PRC FLAR END SEC 18	EACH	3.000				
54213669	PRC FLAR END SEC 24	EACH	16.000				
54213681	PRC FLAR END SEC 36	EACH	6.000				
54214515	PRC FL END S EQ RS 30	EACH	2.000				
54214521	PRC FL END S EQ RS 36	EACH	4.000				
54247170	GRATING-C FL END S 36	EACH	6.000				
54248150	GRT-C FL END S EQV 30	EACH	2.000				
54248160	GRT-C FL END S EQV 36	EACH	4.000				
54248510	CONCRETE COLLAR	CU YD	4.400				
550A0040	STORM SEW CL A 1 10	FOOT	48.100				
550A0050	STORM SEW CL A 1 12	FOOT	1,152.800				
550A0340	STORM SEW CL A 2 12	FOOT	3,550.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0360	STORM SEW CL A 2 15	FOOT	1,710.800				
550A0380	STORM SEW CL A 2 18	FOOT	1,125.400				
550A0410	STORM SEW CL A 2 24	FOOT	1,060.900				
550A5300	SS CL A 2 EQRS 36	FOOT	246.200				
55100500	STORM SEWER REM 12	FOOT	939.300				
55100700	STORM SEWER REM 15	FOOT	307.800				
55100900	STORM SEWER REM 18	FOOT	301.400				
55101200	STORM SEWER REM 24	FOOT	652.100				
55101400	STORM SEWER REM 30	FOOT	195.800				
55101600	STORM SEWER REM 36	FOOT	452.000				
58700300	CONCRETE SEALER	SQ FT	9,149.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	555.000				
60100060	CONC HDWL FOR P DRAIN	EACH	38.000				
60200105	CB TA 4 DIA T1F OL	EACH	1.000				
60201340	CB TA 4 DIA T24F&G	EACH	19.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60218400	MAN TA 4 DIA T1F CL	EACH	11.000				
60221100	MAN TA 5 DIA T1F CL	EACH	2.000				
60234200	INLETS TA T1F OL	EACH	5.000				
60237470	INLETS TA T24F&G	EACH	7.000				
60240210	INLETS TB T1F OL	EACH	8.000				
60240328	INLETS TB T24F&G	EACH	3.000				
60250200	CB ADJUST	EACH	6.000				
60255500	MAN ADJUST	EACH	9.000				
60270050	DR STR T4 W/2 T20F&G	EACH	34.000				
60500040	REMOV MANHOLES	EACH	1.000				
60500050	REMOV CATCH BAS	EACH	7.000				
60500205	FILL CATCH BAS	EACH	11.000				
60600095	CLASS SI CONC OUTLET	CU YD	35.000				
60600605	CONC CURB TB	FOOT	66.000				
60602800	CONC GUTTER TB	FOOT	166.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* 60605000	COMB CC&G TB6.24	FOOT	10,738.000				
* 60608521	COMB CC&G TM2.24	FOOT	759.000				
60618300	CONC MEDIAN SURF 4	SQ FT	47,694.000				
* 63000001	SPBGR TY A 6FT POSTS	FOOT	2,275.000				
* 63000005	SPBGR TY B	FOOT	125.000				
63100045	TRAF BAR TERM T2	EACH	2.000				
63100070	TRAF BAR TERM T5	EACH	1.000				
63100085	TRAF BAR TERM T6	EACH	6.000				
* 63100167	TR BAR TRM T1 SPL TAN	EACH	9.000				
63200310	GUARDRAIL REMOV	FOOT	9,317.000				
63500105	DELINEATORS	EACH	786.000				
63700275	CONC BAR 2F 42HT	FOOT	6,913.000				
63700805	CONC BAR TRANS	FOOT	60.000				
63700900	CONC BARRIER BASE	FOOT	6,973.000				
63801100	MOD BLADE TY GLAR SCR	FOOT	19,175.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
64200105	SHOULDER RUMBLE STRIP	FOOT	24,876.000				
66400105	CH LK FENCE 4	FOOT	2,736.000				
66500105	WOV W FENCE 4	FOOT	12,678.000				
66700205	PERM SURV MKRS T1	EACH	3.000				
66700305	PERM SURV MKRS T2	EACH	1.000				
* 66900200	NON SPL WASTE DISPOSL	CU YD	1,900.000				
* 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
* 66900530	SOIL DISPOSAL ANALY	EACH	4.000				
67000400	ENGR FIELD OFFICE A	CAL MO	40.000				
67100100	MOBILIZATION	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	140.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	88,414.000				
70400100	TEMP CONC BARRIER	FOOT	19,663.000				
70400200	REL TEMP CONC BARRIER	FOOT	18,483.000				
72000100	SIGN PANEL T1	SQ FT	274.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72000200	SIGN PANEL T2	SQ FT	188.000				
72000300	SIGN PANEL T3	SQ FT	3,684.000				
72400100	REMOV SIN PAN ASSY TA	EACH	7.000				
72400310	REMOV SIGN PANEL T1	SQ FT	284.000				
72400320	REMOV SIGN PANEL T2	SQ FT	288.000				
72400330	REMOV SIGN PANEL T3	SQ FT	3,197.000				
72400710	RELOC SIGN PANEL T1	SQ FT	16.000				
72400730	RELOC SIGN PANEL T3	SQ FT	64.000				
72500100	OBJECT MARKER T1	EACH	2.000				
72600100	MILEPOST MKR ASSEMBLY	EACH	2.000				
72700100	STR STL SIN SUP BA	POUND	38,030.000				
72700200	TUB STL SN SUPPORT BA	POUND	335.000				
72900100	METAL POST TY A	FOOT	24.000				
73000100	WOOD SIN SUPPORT	FOOT	796.000				
73300100	OVHD SIN STR-SPAN T1A	FOOT	133.200				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
73301810	OSS WALKWAY TY A	FOOT	88.000				
73400100	CONC FOUNDATION	CU YD	78.000				
73400200	DRILL SHAFT CONC FDN	CU YD	25.600				
73600100	REMOV OH SIN STR-SPAN	EACH	2.000				
73602000	REM OVHD SN STR-BR MT	EACH	1.000				
73700100	REM GR MT SIN SUPPORT	EACH	112.000				
73700200	REM CONC FDN-GR MT	EACH	62.000				
73700300	REM CONC FDN-OVHD	EACH	4.000				
78003100	PREF PL PM TB LTR-SYM	SQ FT	562.000				
78004230	PREF PL PM TB INL L6	FOOT	9,330.000				
78004240	PREF PL PM TB INL L8	FOOT	588.000				
78005110	EPOXY PVT MK LINE 4	FOOT	82,950.000				
78005130	EPOXY PVT MK LINE 6	FOOT	11,321.000				
78005140	EPOXY PVT MK LINE 8	FOOT	950.000				
78005180	EPOXY PVT MK LINE 24	FOOT	298.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78100100	RAISED REFL PAVT MKR	EACH	648.000				
78100300	REPLACEMENT REFLECTOR	EACH	560.000				
78200300	PRISMATIC CURB REFL	EACH	194.000				
78200410	GUARDRAIL MKR TYPE A	EACH	47.000				
78200530	BAR WALL MKR TYPE C	EACH	1,396.000				
78201000	TERMINAL MARKER - DA	EACH	7.000				
78300100	PAVT MARKING REMOVAL	SQ FT	16,200.000				
78300200	RAISED REF PVT MK REM	EACH	560.000				
80400100	ELECT SERV INSTALL	EACH	2.000				
81012600	CON T 2 PVC	FOOT	7,103.000				
81012700	CON T 2 1/2 PVC	FOOT	357.000				
81012800	CON T 3 PVC	FOOT	357.000				
81013000	CON T 4 PVC	FOOT	207.000				
81018500	CON P 2 GALVS	FOOT	1,651.000				
81018600	CON P 2 1/2 GALVS	FOOT	49.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81018700	CON P 3 GALVS	FOOT	192.000				
81018900	CON P 4 GALVS	FOOT	2,640.000				
81100605	CON AT ST 2 PVC GALVS	FOOT	10.000				
81300730	JUN BX SS AS 16X14X6	EACH	1.000				
81400700	HANDHOLE PCC	EACH	22.000				
81400720	DBL HANDHOLE PCC	EACH	3.000				
81603025	UD 2#4 #4G XLPUSE 1	FOOT	8,572.000				
81603035	UD 2#6 #6G XLPUSE 1	FOOT	7,784.000				
81800200	A CBL 2-1C4 MESS WIRE	FOOT	10,132.000				
81900200	TR & BKFIL F ELECT WK	FOOT	23,518.000				
82102400	LUM SV HOR MT 400W	EACH	78.000				
82103400	LUM SV HOR MT PC 400W	EACH	5.000				
82105600	LUM SV HM HOR MT 400W	EACH	92.000				
82107300	UNDERPAS LUM 150W HPS	EACH	12.000				
82500360	LT CONT BASEM 480V100	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
83004600	LT P A 50MH 15DA	EACH	19.000				
83057350	LT P WD 60 CL 4	EACH	21.000				
83057355	LT P WD 60 CL4 15MA	EACH	31.000				
83502300	LT TOWER 100MH LM 4	EACH	8.000				
83502400	LT TOWER 100MH LM 6	EACH	10.000				
83600300	LIGHT POLE FDN 30D	FOOT	133.000				
83700300	LT TOWER FDN 48D	FOOT	225.000				
83800650	BKWY DEV COU SS SCR N	EACH	76.000				
84100110	REM TEMP LIGHT UNIT	EACH	55.000				
84200500	REM LT UNIT SALV	EACH	21.000				
84200804	REM POLE FDN	EACH	21.000				
84500110	REMOV LIGHTING CONTR	EACH	2.000				
84500120	REMOV ELECT SERV INST	EACH	2.000				
84500130	REMOV LTG CONTR FDN	EACH	2.000				
85000200	MAIN EX TR SIG INSTAL	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
85700205	FAC T4 CAB SPL	EACH	4.000				
85700305	FAC T5 CAB SPL	EACH	1.000				
86000105	MASTER CONTROLLER SPL	EACH	1.000				
86200300	UNINTER POWER SUP EXT	EACH	5.000				
86400100	TRANSCEIVER - FIB OPT	EACH	5.000				
87100020	FOCC62.5/125 MM12SM12	FOOT	5,658.000				
87300925	ELCBL C TRACER 14 1C	FOOT	5,658.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	500.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	2,845.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	9,365.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	319.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	15,001.000				
87301804	ELCBL C SERV 6 1C	FOOT	2,141.000				
87301805	ELCBL C SERV 6 2C	FOOT	1,602.000				
87301815	ELCBL C SERV 6 3C	FOOT	886.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87502480	TS POST GALVS 14	EACH	2.000				
87502500	TS POST GALVS 16	EACH	16.000				
87702700	S MAA & P DMA 44 & 50	EACH	1.000				
87702910	STL COMB MAA&P 36	EACH	1.000				
87702930	STL COMB MAA&P 40	EACH	2.000				
87703010	STL COMB MAA&P 56	EACH	1.000				
87703020	STL COMB MAA&P 58	EACH	1.000				
87800100	CONC FDN TY A	FOOT	72.000				
87800150	CONC FDN TY C	FOOT	8.000				
87800415	CONC FDN TY E 36D	FOOT	80.000				
87900200	DRILL EX HANDHOLE	EACH	12.000				
88040070	SH P LED 1F 3S BM	EACH	15.000				
88040090	SH P LED 1F 3S MAM	EACH	18.000				
88040150	SH P LED 1F 5S BM	EACH	3.000				
88102825	PED SH P LED 1F BM CT	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66409

State Job # - C-93-007-04
 PPS NBR - 3-36040-0100
 County Name - KANKAKEE- -
 Code - 91 - -
 District - 3 - -
 Section Number - (46-2)I, HBR, VBR

Project Number
 ACIM-0576/190/306

Route
 FAI 57

* REVISED: APRIL 19, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88200410	TS BACKPLATE L F PLAS	EACH	36.000				
88500100	INDUCTIVE LOOP DETECT	EACH	36.000				
88600100	DET LOOP T1	FOOT	4,623.000				
88700200	LIGHT DETECTOR	EACH	8.000				
88700300	LIGHT DETECTOR AMP	EACH	8.000				
88800100	PED PUSH-BUTTON	EACH	6.000				
89000100	TEMP TR SIG INSTALL	EACH	2.000				
89502200	MOD EX CONTR	EACH	3.000				
89502375	REMOV EX TS EQUIP	EACH	5.000				
89502380	REMOV EX HANDHOLE	EACH	8.000				
89502385	REMOV EX CONC FDN	EACH	8.000				

PAVEMENT MARKING REMOVAL (BDE)	138
PAYMENTS TO SUBCONTRACTORS (BDE)	138
POST CLIPS FOR EXTRUDED ALUMINUM SIGNS (BDE)	139
POST MOUNTING OF SIGNS (BDE).....	139
PRECAST CONCRETE HANDLING HOLES (BDE)	139
PUBLIC CONVENIENCE AND SAFETY (BDE)	141
RAISED REFLECTIVE PAVEMENT MARKERS (BDE).....	141
RECLAIMED ASPHALT PAVEMENT (RAP) (BDE)	141
SEEDING (BDE)	147
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE).....	150
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE).....	153
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	155
SURFACE TESTING OF PAVEMENTS (BDE)	155
TEMPORARY EROSION CONTROL (BDE)	161
TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE)	164
TRAFFIC CONTROL SURVEILLANCE (BDE).....	164
TRAINING SPECIAL PROVISIONS	164
TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE)	166
UTILITY COORDINATION AND CONFLICTS (BDE).....	167
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID).....	172
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	175
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)	179
STORM WATER POLLUTION PREVENTION PLAN.....	183
NOTICE OF INTENT.....	191
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	194

Revised 04/19/2011

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities. .

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.

- A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit.
1. Station 110+00 to Station 112+50 0 to 60 feet RT (Vacant Land, Site 1524V-5, Northeast Quadrant of I-57/IL 50 Interchange, Ramp G) – non-special waste. Contaminants of concern sampling parameters: PNA.
 2. Station 106+00 to Station 107+80 0 to 60 feet RT (Spill Site, Site 1524V-11, I-57 mile marker 315, Ramp G) – non-special waste. Contaminants of concern sampling parameters: PNAs and Arsenic.
 3. Station 114+50 to Station 116+40 0 to 80 feet RT (Vacant Land, Site 1524V-5, Northeast Quadrant of I-57/IL 50 Interchange, Ramp G) – non-special waste. Contaminants of concern sampling parameters: PNAs and Dieldrin.
- B) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill**. Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.

Added 04/19/2011

1. Station 52+00 to Station 54+80 0 to 50 feet RT (Brown and Brown Chevrolet, Site 1524V-6, 1400 Locke Drive, Ramp H) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
2. Station 56+00 to Station 59+00 0 to 60 feet RT (Brown and Brown Chevrolet, Site 1524V-6, 1400 Locke Drive, Ramp H) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
3. Station 86+50 to Station 88+00 0 to 120 feet RT (Spill Site, Site 1524V-11, I-57 mile marker 315) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
4. Station 325+80 to Station 326+25 0 to 180 feet LT (Taylor Chrysler Dodge, Site 1524V-17, 1493 and 1497 North IL 50) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
5. Station 140+50 to Station 141+00 0 to 70 feet LT (Spill Site, Site 1524V-11, I-57 mile marker 315) – non-special waste. Contaminants of concern sampling parameters: Arsenic.

Added 04/19/2011