

90% FED. / 10% STATE
 ROADWAY
 I-57 OVER RR
 SN 046-0015 (AND)
 I-57 OVER RR
 SN 046-0016 (AND)
 ILLINOIS CENTRAL RR
 SN 046-0017 (AND)
 SIGNALS
 (PAID 100%
 BY BRADLEY)
 SAFETY (20%)
 (PAID 100%
 BY BRADLEY)

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0004	0011	0011	0021	0021
• X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1	1				
• X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1				
• X8410118	MAINTENANCE OF TEMPORARY LIGHTING SYSTEM	L SUM	1	1				
• 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5,658	5,658				
• 87301804	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2,141	2,141				
• X8730320	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 20 3/C, TWISTED, SHIELDED	FOOT	2,118	2,118				
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	110,580	110,580				
Z0001058	AGGREGATE SUBGRADE 18"	SQ YD	1,066	1,066				
Z0001060	AGGREGATE SUBGRADE 24"	SQ YD	1,979	1,979				
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1				
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0018800	DRAINAGE SYSTEM	L SUM	1			1		
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4			4		
Z0010911	DRILL AND GROUT #6 TIE BARS	EACH	104	104				
Z0022800	FENCE REMOVAL	FOOT	16,148	16,148				
Z0026407	TEMPORARY SHEET PILING	SQ FT	5,722		5,012	710		
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	9	9				
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2				
Z0030040	IMPACT ATTENUATORS (FULLY REDIRECTIVE, WIDE), TEST LEVEL 2	EACH	6	6				
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4				
Z0030270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	5	5				
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	13	13				
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
• Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1	1				
• 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5,658	5,658				
Z0034105	MATERIAL TRANSFER DEVICE	TON	7,438	7,438				
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	655		302	353		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L SUM						
Z0049802	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 2	L SUM						
Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM						
Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM						
Z0062456	TEMPORARY PAVEMENT	SQ YD	30,332	30,332				
Z0065740	SLOTTED DRAIN 12" WITH VARIABLE SLOT	FOOT	2,490	2,490				
• Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	2				

• DENOTES SPECIALTY ITEM

Rev. 4-18-11

FILE NAME = I:\Dgn\sheet\sq010.dgn	USER NAME = EricG	DESIGNED - JWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1:50	CHECKED - EUG	REVISED -	57					(46-2) I, HBR, VBR	KANKAKEE	558	13	
PLOT DATE = 12/22/2010	DATE - 12/17/10	REVISED -	SCALE: NONE SHEET NO. 10 OF 11 SHEETS STA. TO STA.			CONTRACT NO. 66409						
								FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				