CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES				
				0004	0011	0011	0021	0021
				90% FED./10% STATE				
				ROADWAY	I-57 OVER IL ROUTE 50 SN 046-0014 (SB) SN 046-0015 (NB)	I-57 OVER ILLINOIS CENTRAL RR SN 046-0016 (SB) SN 046-0017 (NB)	SIGNALS (PAID 100% BY BRADLEY)	SAFETY (PAID 100% BY BRADLEY)
				URBAN				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,667	4,667				
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	5,993	5,993				
48300705	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/4"	SQ YD	19,391	19,391				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1			
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1			
50102400	CONCRETE REMOVAL	CU YD	16.9	16.9				
50104650	SLOPE WALL REMOVAL	SQ YD	149	149				
50105220	PIPE CULVERT REMOVAL	FOOT	129.3	129.3				
50157300	PROTECTIVE SHIELD	SQ YD	3,925		2,174	1,751		
50200100	STRUCTURE EXCAVATION	CU YD	1,245		706	539		
50300225	CONCRETE STRUCTURES	CU YD	2,263.6	8.6	1,071	1,184		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2,723		1,325	1,398		
50300260	BRIDGE DECK GROOVING	SQ YD	7,089		3,131	3,958		
50300280	CONCRETE ENCASEMENT	CU YD	35		16	19		
50300300	PROTECTIVE COAT	SQ YD	8,059		3,644	4,415		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.00		0.53	0.47		
50500505	STUD SHEAR CONNECTORS	EACH	34,896		18,198	16,698		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,004,778	1,230	511,310	492,238		
50800515	BAR SPLICERS	EACH	4,647		2,488	2,159		
51100100	SLOPE WALL 4 INCH	SQ YD	1,322		1,174	148		
51201500	FURNISHING STEEL PILES HP10X57	FOOT	3,916		1,914	2,002		
51202305	DRIVING PILES	FOOT	3,916		1,914	2,002		
51203500	TEST PILE STEEL HP10X57	EACH	4		2	2		
51204650	PILE SHOES	EACH	98		46	52		
51500100	NAME PLATES	EACH	4		2	2		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	80		36	44		
52100510	ANCHOR BOLTS, 3/4"	EACH	36		36			
52100520	ANCHOR BOLTS, 1"	EACH	320		144	176		
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1				
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	1	1				
54001007	BOX CULVERT END SECTIONS, CULVERT NO. 7	EACH	1	1				
54002050	EXPANSION BOLTS 3/4 INCH X 9 INCH	EACH	24	24				
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	34.8	34.8				

• DENOTES SPECIALTY ITEM

Rev.

FILE NAME = I:\Dgn\sheets\sq003.dgn	USER NAME = EricG	DESIGNED - JWM	REVISED -
		DRAWN - JWM	REVISED -
	PLOT SCALE = 1:50	CHECKED - EJG	REVISED -
	PLOT DATE = 12/22/2010	DATE - 12/17/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 3 OF 11 SHEETS | STA. | TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(46-2) I, HBR, VBR	KANKAKEE	558	6

CONTRACT NO. 66409

FED. ROAD DIST. NO. 3 | ILLINOIS | FED. AID PROJECT