

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE FUNDS 100% STATE STRUCTURE 0014 RURAL
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	16	16
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	1059.4	1059.4
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	135	135
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	426	426
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	260	260
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	260	260
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	1065.3	1065.3
Z0007122	REMOV <sup>ING</sup> AND RE-ERECT <sup>ING</sup> EXISTING RAILING	FOOT	142	142
X4400196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	16.7	16.7
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	5	5
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

FILE NAME =	USER NAME = potelyj	DESIGNED - RON WOODSHANK	REVISED -
ca:\pw\work\pwidot\potelyj\d0257632\0368	26-shd-details.DGN	DRAWN - RON WOODSHANK	REVISED -
	PLOT SCALE = 100.0/431 / IN.	CHECKED -	REVISED -
	PLOT DATE = Feb 24, 2011 - 03:58:06 PM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ SHEET NO. 1 OF 1 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(115-BRI)	FORD	11	3
CONTRACT NO. 66B26			ILLINOIS FED. AID PROJECT	

Rev.