

LOCATION			63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	63200310 GUARDRAIL REMOVAL	63301210 REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	78200410 GUARDRAIL MARKERS, TYPE A	78201000 TERMINAL MARKER - DIRECT APPLIED
STATION	STATION	OFFSET	(FOOT)	(EACH)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)
755+55.00	756+57.00	LT				102			
755+56.00	756+57.00	RT				101			
761+10.00	762+12.00	LT				102			
761+10.00	761+87.00	RT				77			
766+40.00	767+00.00	LT				60			
766+40.00	769+68.00	RT				328			
762+37.50	762+87.50	LT			1				1
762+87.50	767+00.00	LT	412.5						
767+00.00	773+25.00	LT					625.0	7	
753+80.67	762+05.83	LT						10	
753+80.67	754+30.67	LT			1				1
754+30.67	755+43.17	LT	112.5						
755+43.17	755+86.92	LT		1					
760+87.08	761+30.83	LT		1					
761+30.83	761+55.83	LT	25.0						
761+55.83	762+05.83	LT			1				1
753+68.17	761+93.33	RT						10	
753+68.17	754+18.17	RT			1				1
754+18.17	755+43.17	RT	125.0						
755+43.17	755+86.92	RT		1					
760+87.08	761+30.83	RT		1					
761+30.83	761+43.33	RT	12.5						
761+43.33	761+93.33	RT			1				1
TOTAL			687.5	4	5	770	625.0	27	5

LOCATION			Z0028462 GEOTEXTILE RETAINING WALL	60107600 PIPE UNDERDRAINS 4"	60108100 PIPE UNDERDRAINS 4" (SPECIAL)	60100060 CONCRETE HEADWALLS FOR PIPE DRAINS
STATION	STATION	OFFSET	(SQ FT)	(FOOT)	(FOOT)	(EACH)
755+33.00	755+87.42	RT	107			
755+33.00	755+87.00	4' RT		54		
755+33.00	755+87.00	RT			36	
755+87.00		43' RT				1
761+02.58	761+96.00	RT	196			
761+02.58	761+96.00	4' RT		94		
761+55.00	761+55.00	RT			32	
761+55.00		39' RT				1
TOTAL			303	148	68	2

LOCATION	NUMBER OF POSTS	72800100 TELESCOPING STEEL SIGN SUPPORTS (FOOT)	NUMBER OF SIGN PANELS	72000100 SIGN PANEL - TYPE 1 SQ FT
RT. STA. 764+63 TO 771+80 (AT 200' SPACING)	4	60	8	40
TOTAL		60		40

Notes:

- SIGN DESIGNATIONS ARE W1-8R-2430 and W1-8L-2430. (2' X2.5' = 5 SQ FT PER PANEL)
- SEE HIGHWAY STANDARDS 728001 AND 729001 FOR INSTALLATION DETAILS
- ALL SIGN PANELS SHALL BE BOLTED TO METAL POSTS WITH STAINLESS STEEL FASTENERS.
- CONTACT TRAFFIC OPERATIONS AREA TECHNICIAN RANDY HARTZ AT (309) 734-3721 TO VERIFY POST LOCATIONS.

USER NAME = gjameson  
PLOT SCALE = 100.0000' / IN.  
PLOT DATE = 12/21/2010

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

**WHKS & CO.**  
ENGINEERING  
7018 KINGSMILL CT.,  
SPRINGFIELD, IL  
(217) 483-9457  
DESIGN FIRM #184001038

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 4 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
542	105BR-1	MCDONOUGH	117	17
CONTRACT NO. 68482				
ILLINOIS FED. AID PROJECT				