

LOCATION			TYPE	COLOR	70300100 SHORT TERM PAVEMENT MARKING (FOOT)	70300220 TEMPORARY PAVEMENT MARKING - LINE 4" (FOOT)	70300280 TEMPORARY PAVEMENT MARKING - LINE 24" (FOOT)	70300520 PAVEMENT MARKING TAPE, TYPE III 4" (FOOT)	70301000 WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	78001110 PAINT PAVEMENT MARKING - LINE 4" (FOOT)	78100100 RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	78300100 PAVEMENT MARKING REMOVAL (SQ FT)
STAGE I												
749+77	752+00	CL										20
751+47	767+67	LT										540
766+50	769+18	CL										179
STAGE II												
749+77		RT	SOLID	WHITE			13					
749+87	768+58	RT	SOLID	YELLOW		1,871						
749+87	751+50	RT						55				
767+25	768+58							45				
751+47	767+67	LT	SOLID	YELLOW		1,620						
769+18		LT	SOLID	WHITE			13					
WINTER SHUT DOWN												
750+35	755+68.42		SOLID	YELLOW		533						
761+15.58	769+08		SOLID	YELLOW		792						
751+45	755+68.42		SOLID	YELLOW		423						
761+15.58	767+25		SOLID	YELLOW		609						
STAGE III												
749+77		RT	SOLID	WHITE				26				
750+35	755+68.42		SOLID	YELLOW		533		178				
755+68.42	761+15.58	RT	SOLID	YELLOW			547	183				
761+15.58	769+08		SOLID	YELLOW		792		264				
751+45	755+68.42		SOLID	YELLOW		423		141				
755+68.42	761+15.58	RT	SOLID	YELLOW			547	183				
761+15.58	767+25		SOLID	YELLOW		609		203				
769+18		LT	SOLID	WHITE				26				
STAGE IV												
751+00	773+25	CL	SKIP DASH	YELLOW	224			150				
ASSUME THREE APPLICATIONS DURING CONSTRUCTION OF 4" BINDER COURSE LIFTS SOUTH OF LAMOINE RIVER												
751+00	755+68.42	CL	SKIP DASH	YELLOW	144			96				
ASSUME EIGHT APPLICATIONS DURING CONSTRUCTION OF 4" BINDER COURSE LIFTS NORTH OF LAMOINE RIVER												
761+15.58	770+50	CL	SKIP DASH	YELLOW	768			512				
751+00	773+25	LT	SOLID	WHITE					2,225			
751+00	768+50	CL	SKIP DASH	YELLOW					440			
761+40	768+50	CL	SOLID	YELLOW					710			
768+50	773+25	CL	DOUBLE SOLID	YELLOW					950			
751+00	773+25	RT	SOLID	WHITE					2,225			
751+00	755+68.42	CL								6		
761+15.58	773+25	CL								15		
TOTAL					1,136	8,205	26	1,094	2,062	6,550	21	739

USER NAME = g.jamison
PLOT SCALE = 100,0000 / IN.
PLOT DATE = 12/21/2010

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

WHKS & CO.
ENGINEERING
7018 KINGSMILL CT.,
SPRINGFIELD, IL
(217) 483-9457
DESIGN FIRM #184001038

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 5 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
542	105BR-1	MCDONOUGH	117	18
CONTRACT NO. 68482				
ILLINOIS FED. AID PROJECT				