

COMMITMENTS

No Commitments have been made for this project

GENERAL NOTES

All Metalizing shall be as specified in the Special Provision for " Field Thermal Spraying Metalizing " All beams, brackets and all other structural steel shall be cleaned per Near White Blast Cleaning – SSPC SP 10 according to the following schedule:

Bridge No. 1 – 4 – All beams, bearings, brackets and all other structural steel within 5 feet (as measured along the centerline of the beam) of either side of the deck joints.

The final finish coat shall be according to the following schedule:

Bridge 1 Shall be Blue (Munsell No.10B 36)

Bridge 2 – 4 Shall be Green (Munsell No.7.5G 48)

Sealer and Top Coat Shall be from the approved list from table one (1) of the Special Provisions

AIR MONITORS

Location 1 – (1)

Locations 2 – 4 (0)

QP1 & QP2 Required for this Project.

FILE NAME = 68996 4-29-2011.dgn	USER NAME = inglistj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	F.A. RTE. _____	SECTION _____	COUNTY _____	TOTAL SHEETS _____	SHEET NO. _____	
		DRAWN -	REVISED -						VAR 04 Bridge Metalizing 201	FULTON	19	3	
		CHECKED -	REVISED -										
		DATE -	REVISED -										
	PLOT SCALE = 28.7728' / IN.												
	PLOT DATE = 2/14/2011												
ILLINOIS FED. AID PROJECT													