

SCHEDULE OF QUANTITIES

PATCHING SCHEDULE						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
93+71	EB	6.0	13.0	8.25	8.7	4.0
93+71	WB	6.0	13.0	8.25	8.7	4.0
96+90	EB	6.0	13.0	8.25	8.7	4.0
102+00	WB	6.0	13.0	8.25	8.7	4.0
102+49	WB	4.0	13.0	8.25	5.8	2.7
102+57	WB	4.0	13.0	8.25	5.8	2.7
102+65	WB	4.0	13.0	8.25	5.8	2.7
102+79	EB	10.0	13.0	8.25	14.4	6.7
103+13	EB	6.0	13.0	8.25	8.7	4.0
105+87	WB	8.0	13.0	8.25	11.6	5.3
112+88	EB	8.0	13.0	8.25	11.6	5.3
115+75	EB	8.0	13.0	8.25	11.6	5.3
115+75	WB	12.0	13.0	8.25	17.3	8.0
126+39	EB	10.0	13.0	8.25	14.4	6.7
126+39	WB	6.0	13.0	8.25	8.7	4.0
132+90	EB	5.0	13.0	8.25	7.2	3.3
132+90	WB	4.0	13.0	8.25	5.8	2.7
142+19	EB	15.0	6.5	8.25	10.8	5.0
142+19	WB	15.0	6.5	8.25	10.8	5.0
147+52	EB	6.0	13.0	8.25	8.7	4.0
147+52	WB	6.0	13.0	8.25	8.7	4.0
147+99	WB	4.0	13.0	8.25	5.8	2.7
148+07	EB	30.0	6.5	8.25	21.7	10.0
148+07	WB	4.0	13.0	8.25	5.8	2.7
148+15	WB	4.0	13.0	8.25	5.8	2.7
150+37	EB	10.0	13.0	8.25	14.4	6.7
150+37	WB	10.0	13.0	8.25	14.4	6.7
157+80	EB	8.0	13.0	8.25	11.6	5.3
157+80	WB	8.0	13.0	8.25	11.6	5.3
159+40	WB	8.0	13.0	8.25	11.6	5.3
159+48	WB	4.0	13.0	8.25	5.8	2.7
161+59	EB	10.0	6.5	8.25	7.2	3.3
161+59	WB	25.0	13.0	8.25	36.1	16.7
163+34	EB	5.0	13.0	8.25	7.2	3.3
163+34	WB	5.0	13.0	8.25	7.2	3.3
166+66	WB	10.0	13.0	8.25	14.4	6.7
173+72	WB	6.0	13.0	8.25	8.7	4.0
175+10	EB	8.0	13.0	8.25	11.6	5.3
175+10	WB	8.0	13.0	8.25	11.6	5.3
180+55	WB	30.0	13.0	8.25	43.3	20.0
180+63	EB	15.0	13.0	8.25	21.7	10.0
187+68	EB	4.0	13.0	8.25	5.8	2.7
187+68	WB	8.0	13.0	8.25	11.6	5.3
187+78	WB	4.0	13.0	8.25	5.8	2.7
188+86	EB	4.0	13.0	8.25	5.8	2.7
189+75	EB	6.0	13.0	8.25	8.7	4.0

PATCHING SCHEDULE (CONT.)						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
189+75	WB	6.0	13.0	8.25	8.7	4.0
195+01	EB	15.0	13.0	8.25	21.7	10.0
195+01	WB	6.0	13.0	8.25	8.7	4.0
198+30	EB	6.0	13.0	8.25	8.7	4.0
198+47	EB	6.0	13.0	8.25	8.7	4.0
198+30	WB	4.0	13.0	8.25	5.8	2.7
198+47	WB	4.0	13.0	8.25	5.8	2.7
198+55	WB	4.0	13.0	8.25	5.8	2.7
202+61	EB	8.0	13.0	8.25	11.6	5.3
202+61	WB	8.0	13.0	8.25	11.6	5.3
203+04	WB	6.0	13.0	8.25	8.7	4.0
205+61	WB	10.0	13.0	8.25	14.4	6.7
205+85	EB	4.0	13.0	8.25	5.8	2.7
205+96	EB	6.0	13.0	8.25	8.7	4.0
205+96	WB	15.0	13.0	8.25	21.7	10.0
213+67	EB	6.0	13.0	8.25	8.7	4.0
213+83	EB	10.0	6.5	8.25	7.2	3.3
214+37	WB	40.0	6.5	8.25	28.9	13.3
220+92	EB	8.0	13.0	8.25	11.6	5.3
220+92	WB	8.0	13.0	8.25	11.6	5.3
228+43	EB	15.0	13.0	8.25	21.7	10.0
228+43	WB	15.0	13.0	8.25	21.7	10.0
234+56	WB	10.0	13.0	8.25	14.4	6.7
260+88	EB	10.0	13.0	8.25	14.4	6.7
263+72	EB	6.0	13.0	8.25	8.7	4.0
263+72	WB	6.0	13.0	8.25	8.7	4.0
266+90	EB	6.0	13.0	8.25	8.7	4.0
267+02	EB	6.0	13.0	8.25	8.7	4.0
267+02	WB	20.0	13.0	8.25	28.9	13.3
269+48	EB	4.0	13.0	8.25	5.8	2.7
269+58	EB	4.0	13.0	8.25	5.8	2.7
269+48	WB	4.0	13.0	8.25	5.8	2.7
269+58	WB	4.0	13.0	8.25	5.8	2.7
269+68	WB	4.0	13.0	8.25	5.8	2.7
270+05	EB	6.0	13.0	8.25	8.7	4.0
275+63	EB	20.0	6.5	8.25	14.4	6.7
278+25	WB	6.0	13.0	8.25	8.7	4.0
281+93	EB	10.0	13.0	8.25	14.4	6.7
281+93	WB	10.0	13.0	8.25	14.4	6.7
282+08	WB	15.0	6.5	8.25	10.8	5.0
290+35	WB	15.0	13.0	8.25	21.7	10.0
293+80	EB	10.0	13.0	8.25	14.4	6.7
293+80	WB	10.0	13.0	8.25	14.4	6.7
301+73	WB	4.0	13.0	8.25	5.8	2.7
301+90	WB	6.0	13.0	8.25	8.7	4.0
286+39	EB	8.0	13.0	8.25	11.6	5.3

FILE NAME =	USER NAME = oglebj	DESIGNED -	REVISED -
ct:\pw\work\p\dot\oglebj\d0106513\0570662\shtr\schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 2/22/2011		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	(113RS-4, 124RS)	DEWITT	153	18
CONTRACT NO. 70660			ILLINOIS FED. AID PROJECT	