

SCHEDULE OF QUANTITIES

PATCHING SCHEDULE (CONT.)						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
415+45	EB	4.0	13.0	8.25	5.8	2.7
415+45	WB	4.0	13.0	8.25	5.8	2.7
416+59	EB	10.0	13.0	8.25	14.4	6.7
416+59	WB	15.0	13.0	8.25	21.7	10.0
416+76	EB	4.0	13.0	8.25	5.8	2.7
416+76	WB	4.0	13.0	8.25	5.8	2.7
416+89	EB	4.0	13.0	8.25	5.8	2.7
416+89	WB	4.0	13.0	8.25	5.8	2.7
417+22	EB	4.0	13.0	8.25	5.8	2.7
417+22	WB	4.0	13.0	8.25	5.8	2.7
417+40	EB	4.0	13.0	8.25	5.8	2.7
417+40	WB	4.0	13.0	8.25	5.8	2.7
417+51	EB	4.0	13.0	8.25	5.8	2.7
417+51	WB	4.0	13.0	8.25	5.8	2.7
417+83	WB	4.0	13.0	8.25	5.8	2.7
418+12	EB	6.0	13.0	8.25	8.7	4.0
418+12	WB	6.0	13.0	8.25	8.7	4.0
418+25	EB	4.0	13.0	8.25	5.8	2.7
418+25	WB	4.0	13.0	8.25	5.8	2.7
418+91	EB	6.0	13.0	8.25	8.7	4.0
418+91	WB	6.0	13.0	8.25	8.7	4.0
420+43	EB	12.0	6.5	8.25	8.7	4.0
420+43	WB	4.0	13.0	8.25	5.8	2.7
420+63	EB	12.0	6.5	8.25	8.7	4.0
420+63	WB	4.0	13.0	8.25	5.8	2.7
421+57	EB	4.0	13.0	8.25	5.8	2.7
421+57	WB	4.0	13.0	8.25	5.8	2.7
421+95	EB	4.0	13.0	8.25	5.8	2.7
421+95	WB	4.0	13.0	8.25	5.8	2.7
422+88	EB	8.0	13.0	8.25	11.6	5.3
422+88	WB	8.0	13.0	8.25	11.6	5.3
426+43	EB	10.0	13.0	8.25	14.4	6.7
426+43	WB	4.0	13.0	8.25	5.8	2.7
426+55	WB	6.0	13.0	8.25	8.7	4.0
429+04	EB	4.0	13.0	8.25	5.8	2.7
429+04	WB	4.0	13.0	8.25	5.8	2.7
429+36	EB	4.0	13.0	8.25	5.8	2.7
429+36	WB	4.0	13.0	8.25	5.8	2.7
430+39	WB	10.0	13.0	8.25	14.4	6.7
431+36	WB	4.0	13.0	8.25	5.8	2.7
435+31	EB	8.0	13.0	8.25	11.6	5.3
435+31	WB	4.0	13.0	8.25	5.8	2.7
438+88	EB	4.0	13.0	8.25	5.8	2.7
438+88	WB	8.0	13.0	8.25	11.6	5.3

PATCHING SCHEDULE (CONT.)						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
440+30	EB	4.0	13.0	8.25	5.8	2.7
440+30	WB	4.0	13.0	8.25	5.8	2.7
441+33	EB	15.0	13.0	8.25	21.7	10.0
442+16	EB	4.0	13.0	8.25	5.8	2.7
442+16	WB	4.0	13.0	8.25	5.8	2.7
446+57	EB	4.0	13.0	8.25	5.8	2.7
446+89	EB	6.0	13.0	8.25	8.7	4.0
446+89	WB	4.0	13.0	8.25	5.8	2.7
447+85	EB	6.0	13.0	8.25	8.7	4.0
450+13	WB	8.0	13.0	8.25	11.6	5.3
450+30	WB	6.0	13.0	8.25	8.7	4.0
450+99	EB	15.0	13.0	8.25	21.7	10.0
450+99	WB	4.0	13.0	8.25	5.8	2.7
452+30	EB	6.0	13.0	8.25	8.7	4.0
452+30	WB	6.0	13.0	8.25	8.7	4.0
452+62	EB	25.0	13.0	8.25	36.1	16.7
452+62	WB	15.0	13.0	8.25	21.7	10.0
453+42	EB	4.0	13.0	8.25	5.8	2.7
453+42	WB	4.0	13.0	8.25	5.8	2.7
453+63	EB	8.0	13.0	8.25	11.6	5.3
453+63	WB	4.0	13.0	8.25	5.8	2.7
453+73	WB	4.0	13.0	8.25	5.8	2.7
454+10	EB	6.0	13.0	8.25	8.7	4.0
454+27	EB	6.0	13.0	8.25	8.7	4.0
454+27	WB	6.0	13.0	8.25	8.7	4.0
454+96	EB	6.0	13.0	8.25	8.7	4.0
454+96	WB	6.0	13.0	8.25	8.7	4.0
456+59	EB	4.0	13.0	8.25	5.8	2.7
456+59	WB	6.0	13.0	8.25	8.7	4.0
457+13	EB	6.0	13.0	8.25	8.7	4.0
459+00	EB	4.0	13.0	8.25	5.8	2.7
459+10	EB	6.0	13.0	8.25	8.7	4.0
459+10	WB	12.0	13.0	8.25	17.3	8.0
459+25	EB	8.0	13.0	8.25	11.6	5.3
459+25	WB	4.0	13.0	8.25	5.8	2.7
459+87	EB	6.0	13.0	8.25	8.7	4.0
459+87	WB	6.0	13.0	8.25	8.7	4.0
460+22	EB	4.0	13.0	8.25	5.8	2.7
460+22	WB	4.0	13.0	8.25	5.8	2.7
460+33	EB	4.0	13.0	8.25	5.8	2.7
460+33	WB	4.0	13.0	8.25	5.8	2.7
460+79	EB	4.0	13.0	8.25	5.8	2.7
460+79	WB	4.0	13.0	8.25	5.8	2.7
461+27	EB	6.0	13.0	8.25	8.7	4.0
461+27	WB	6.0	13.0	8.25	8.7	4.0

FILE NAME =	USER NAME = oglobj	DESIGNED -	REVISED -
cc:\pk_work\pwidot\oglobj\d0106513\0570669-sht-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 48.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 2/22/2011		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 721	SECTION (113RS-4, 124RS)	COUNTY DEWITT	TOTAL SHEETS 153	SHEET NO. 20
CONTRACT NO. 70660				
ILLINOIS FED. AID PROJECT				