

# SCHEDULE OF QUANTITIES

PATCHING SCHEDULE (CONT.)						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
461+96	EB	8.0	13.0	8.25	11.6	5.3
461+96	WB	6.0	13.0	8.25	8.7	4.0
463+00	EB	4.0	13.0	8.25	5.8	2.7
463+10	EB	6.0	13.0	8.25	8.7	4.0
463+28	EB	8.0	13.0	8.25	11.6	5.3
463+40	EB	4.0	13.0	8.25	5.8	2.7
463+75	EB	4.0	13.0	8.25	5.8	2.7
463+84	EB	4.0	13.0	8.25	5.8	2.7
465+70	EB	4.0	13.0	8.25	5.8	2.7
465+70	WB	4.0	13.0	8.25	5.8	2.7
465+84	EB	4.0	13.0	8.25	5.8	2.7
465+84	WB	4.0	13.0	8.25	5.8	2.7
466+39	EB	4.0	13.0	8.25	5.8	2.7
466+39	WB	4.0	13.0	8.25	5.8	2.7
468+23	EB	4.0	13.0	8.25	5.8	2.7
468+23	WB	4.0	13.0	8.25	5.8	2.7
472+22	EB	4.0	13.0	8.25	5.8	2.7
472+22	WB	4.0	13.0	8.25	5.8	2.7
477+84	EB	4.0	13.0	8.25	5.8	2.7
477+84	WB	4.0	13.0	8.25	5.8	2.7
477+92	EB	4.0	13.0	8.25	5.8	2.7
478+00	EB	15.0	13.0	8.25	21.7	10.0
478+00	WB	15.0	13.0	8.25	21.7	10.0
478+10	EB	4.0	13.0	8.25	5.8	2.7
479+49	EB	4.0	13.0	8.25	5.8	2.7
479+49	WB	4.0	13.0	8.25	5.8	2.7
481+45	EB	4.0	13.0	8.25	5.8	2.7
481+45	WB	4.0	13.0	8.25	5.8	2.7
486+65	EB	10.0	13.0	8.25	14.4	6.7
486+65	WB	10.0	13.0	8.25	14.4	6.7
486+74	EB	10.0	13.0	8.25	14.4	6.7
486+74	WB	10.0	13.0	8.25	14.4	6.7
487+34	EB	10.0	13.0	8.25	14.4	6.7
487+34	WB	10.0	6.5	8.25	7.2	3.3
487+71	WB	6.0	13.0	8.25	8.7	4.0
488+46	WB	6.0	13.0	8.25	8.7	4.0
495+68	EB	4.0	13.0	8.25	5.8	2.7
495+68	WB	6.0	13.0	8.25	8.7	4.0
496+89	WB	6.0	13.0	8.25	8.7	4.0
497+11	EB	4.0	13.0	8.25	5.8	2.7
497+11	WB	10.0	13.0	8.25	14.4	6.7
497+25	WB	4.0	13.0	8.25	5.8	2.7
498+25	WB	4.0	13.0	8.25	5.8	2.7
498+35	EB	8.0	13.0	8.25	11.6	5.3
498+35	WB	10.0	13.0	8.25	14.4	6.7

PATCHING SCHEDULE (CONT.)						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
501+24	EB	10.0	13.0	8.25	14.4	6.7
501+24	WB	4.0	13.0	8.25	5.8	2.7
502+40	EB	4.0	13.0	8.25	5.8	2.7
502+40	WB	4.0	13.0	8.25	5.8	2.7
510+31	EB	4.0	13.0	8.25	5.8	2.7
510+31	WB	4.0	13.0	8.25	5.8	2.7
510+99	WB	4.0	13.0	8.25	5.8	2.7
511+07	EB	4.0	13.0	8.25	5.8	2.7
511+07	WB	4.0	13.0	8.25	5.8	2.7
511+58	EB	4.0	13.0	8.25	5.8	2.7
511+58	WB	4.0	13.0	8.25	5.8	2.7
512+40	EB	12.0	13.0	8.25	17.3	8.0
512+40	WB	12.0	13.0	8.25	17.3	8.0
512+83	EB	4.0	13.0	8.25	5.8	2.7
512+83	WB	4.0	13.0	8.25	5.8	2.7
516+34	EB	20.0	13.0	8.25	28.9	13.3
516+34	WB	6.0	13.0	8.25	8.7	4.0
516+45	WB	4.0	13.0	8.25	5.8	2.7
518+36	WB	8.0	13.0	8.25	11.6	5.3
518+98	EB	4.0	13.0	8.25	5.8	2.7
518+98	WB	4.0	13.0	8.25	5.8	2.7
520+31	EB	4.0	13.0	8.25	5.8	2.7
520+31	WB	4.0	13.0	8.25	5.8	2.7
522+58	EB	4.0	13.0	8.25	5.8	2.7
522+58	WB	4.0	13.0	8.25	5.8	2.7
523+28	EB	8.0	13.0	8.25	11.6	5.3
523+28	WB	8.0	13.0	8.25	11.6	5.3
524+83	WB	20.0	13.0	8.25	28.9	13.3
524+95	WB	4.0	13.0	8.25	5.8	2.7
528+37	WB	10.0	13.0	8.25	14.4	6.7
535+00	EB	6.0	13.0	8.25	8.7	4.0
535+00	WB	8.0	13.0	8.25	11.6	5.3
535+10	WB	8.0	13.0	8.25	11.6	5.3
535+49	EB	8.0	13.0	8.25	11.6	5.3
535+49	WB	8.0	13.0	8.25	11.6	5.3
545+13	EB	18.0	13.0	8.25	26.0	12.0
545+13	WB	18.0	13.0	8.25	26.0	12.0
549+03	WB	4.0	13.0	8.25	5.8	2.7
549+13	WB	4.0	13.0	8.25	5.8	2.7
551+10	WB	4.0	13.0	8.25	5.8	2.7
551+53	WB	6.0	13.0	8.25	8.7	4.0
552+06	WB	6.0	13.0	8.25	8.7	4.0
552+48	EB	4.0	13.0	8.25	5.8	2.7
552+48	WB	4.0	13.0	8.25	5.8	2.7
555+81	WB	4.0	13.0	8.25	5.8	2.7

FILE NAME =	USER NAME = eglebj	DESIGNED -	REVISED -
c:\pw\work\pws\d01\oglebj\d0106513\0578682-sht-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 48.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/22/2011	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES</b>			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 721	SECTION (113RS-4, 124RS)	COUNTY DEWITT	TOTAL SHEETS 153	SHEET NO. 21
CONTRACT NO. 70660				
ILLINOIS FED. AID PROJECT				