

SCHEDULE OF QUANTITIES

PATCHING SCHEDULE (CONT.)						
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	#5000105	X4421000
					PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
617+89	EB	4.0	13.0	8.25	5.8	2.7
617+89	WB	4.0	13.0	8.25	5.8	2.7
618+68	EB	4.0	13.0	8.25	5.8	2.7
618+68	WB	4.0	13.0	8.25	5.8	2.7
618+88	EB	4.0	13.0	8.25	5.8	2.7
619+23	EB	4.0	13.0	8.25	5.8	2.7
619+23	WB	4.0	13.0	8.25	5.8	2.7
619+35	EB	4.0	13.0	8.25	5.8	2.7
619+35	WB	4.0	13.0	8.25	5.8	2.7
619+65	EB	4.0	13.0	8.25	5.8	2.7
619+65	WB	4.0	13.0	8.25	5.8	2.7
619+87	EB	4.0	13.0	8.25	5.8	2.7
619+87	WB	4.0	13.0	8.25	5.8	2.7
620+01	EB	10.0	13.0	8.25	14.4	6.7
620+01	WB	4.0	13.0	8.25	5.8	2.7
620+20	EB	4.0	13.0	8.25	5.8	2.7
620+20	WB	4.0	13.0	8.25	5.8	2.7
620+36	EB	4.0	13.0	8.25	5.8	2.7
620+36	WB	4.0	13.0	8.25	5.8	2.7
620+47	EB	15.0	13.0	8.25	21.7	10.0
620+47	WB	15.0	13.0	8.25	21.7	10.0
620+96	EB	12.0	13.0	8.25	17.3	8.0
620+96	WB	12.0	13.0	8.25	17.3	8.0
621+47	EB	6.0	13.0	8.25	8.7	4.0
621+47	WB	6.0	13.0	8.25	8.7	4.0
621+91	EB	6.0	13.0	8.25	8.7	4.0
621+91	WB	6.0	13.0	8.25	8.7	4.0
622+35	EB	6.0	13.0	8.25	8.7	4.0
622+35	WB	6.0	13.0	8.25	8.7	4.0
TOTAL =					4714.8	2178.3
USE =					4715.0	2179.0

28000400 PERIMETER EROSION BARRIER

SIDE	STATION	TO	STATION	FOOT
LT & RT	179+50.00	TO	181+25.00	350.0
RT	217+00.00	TO	220+50.00	350.0
LT	218+50.00	TO	219+50.00	100.0
RT	225+00.00	TO	226+00.00	100.0
LT	226+50.00	TO	228+00.00	150.0
RT	227+50.00	TO	228+25.00	75.0
LT & RT	251+00.00	TO	252+50.00	300.0
RT	273+00.00	TO	274+00.00	100.0
LT	323+50.00	TO	324+50.00	100.0
LT & RT	334+50.00	TO	339+00.00	900.0
LT	358+00.00	TO	359+50.00	150.0
RT	358+00.00	TO	361+00.00	300.0
LT & RT	402+00.00	TO	403+50.00	300.0
LT & RT	468+00.00	TO	469+50.00	300.0
TOTAL =				3575.0
USE =				3575.0

STATION	XZ193400 SURVEY MARKER TY 2, (SPECIAL) (EACH)	Z0070100 SURVEY MONUMENT COVER ASSEMBLY (EACH)
93+14.45 0.13' RT		1.0
189+07.74	1.0	
200+76.87	1.0	
230+11.82 (BK)	1.0	
230+21.51 (AH)		
290+55.30	1.0	
302+25.59	1.0	
302+35.00 (BK)	1.0	
288+01.80 (AH)		
305+56.80 14.90' RT		1.0
358+32.52 11.73' RT		1.0
433+14.12	1.0	
443+44.68	1.0	
453+75.12	1.0	
519+76.16 0.58' LT		1.0
522+15.46	1.0	
532+15.46	1.0	
542+15.14	1.0	
552+15.14	1.0	
562+14.84	1.0	
TOTAL =		14.0
TOTAL =		4.0

PAVEMENT MARKING SCHEDULE

78001110							70300100					78100100				70300220						70301000												
PAINT PAVEMENT MARKING - LINE 4"							SHORT TERM PAVEMENT MARKING					RAISED REFLECTIVE PAVEMENT MARKERS				TEMPORARY PAVEMENT MARKING - LINE 4"						WORK ZONE PAVEMENT MARKING REMOVAL												
STATION	TO	STATION	(FEET)	(WHITE) (SOLID)	(YELLOW) (SOLID)	(YELLOW) (DASH)	STATION	TO	STATION	APPS	LENGTH (FOOT)	STATION	TO	STATION	RATE (FEET)	(EACH)	STATION	TO	STATION	(FEET)	(WHITE) (SOLID)	(YELLOW) (SOLID)	(YELLOW) (DASH)	STATION	TO	STATION	(FOOT)	AREA (SQ FT)						
92+50.00	TO	230+11.82	13,761.8	27,523.6	1,362.0	3,440.5	92+50.00	TO	133+08.51	3.0	1217.6	92+50.00	TO	230+11.82	80.0	172.0	92+50.00	TO	230+11.82	13761.8	27523.6	1,362.0	3440.5	92+50.00	TO	230+11.82	1376.2	454.1						
230+21.51	TO	238+00.00	778.5	1,557.0	780.0	194.6	133+08.51	TO	148+12.89	2.0	300.9	230+21.51	TO	238+00.00	80.0	10.0	230+21.51	TO	238+00.00	778.5	1557.0	780.0	194.6	230+21.51	TO	238+00.00	77.8	25.7						
249+00.00	TO	302+35.00	5,335.0	10,670.0	4,560.0	1,333.8	148+12.89	TO	228+25.73	3.0	2403.9	249+00.00	TO	302+35.00	80.0	67.0	249+00.00	TO	302+35.00	5335.0	10670.0	4,560.0	1333.8	249+00.00	TO	302+35.00	533.5	176.1						
286+01.80	TO	623+07.00	33,705.2	67,410.4	7,419.0	8,426.3	228+25.73	TO	238+00.00	2.0	194.9	286+01.80	TO	623+07.00	80.0	421.0	286+01.80	TO	623+07.00	33705.2	67410.4	7,419.0	8426.3	286+01.80	TO	623+07.00	3370.5	1112.3						
TOTAL =							107161.0	14121.0	13395.1	249+00.00	TO	252+02.44	3.0	90.7	TOTAL =				670.0	TOTAL =						107161.0	14121.0	13395.1	TOTAL =					1768.2
USE =							107161.0	14121.0	13396.0	252+02.44	TO	263+47.14	2.0	228.9	USE =				670.0	USE =						107161.0	14121.0	13396.0	USE =					1769.0
TOTAL LENGTH =							134678.0			263+47.14	TO	302+35.00	3.0	1166.4	TOTAL LENGTH =						134678.0													
							286+01.80	TO	345+62.66	3.0	1788.3																							
							345+62.66	TO	355+28.37	2.0	193.1																							
							355+28.37	TO	360+00.00	3.0	141.5																							
							360+00.00	TO	373+16.50	2.0	263.3																							
							373+16.50	TO	623+07.00	3.0	7497.2																							
							TOTAL =				15486.5																							
							USE =				15487.0																							

NOTE: QUANTITIES FOR SOLID YELLOW LINES ARE ESTIMATED FROM FIELD MEASUREMENTS, LOCATIONS SHOULD BE VERIFIED IN THE FIELD PRIOR TO REMOVAL.