

SUMMARY OF QUANTITIES

LOCATION OF WORK:

CH 19 (FICKLIN ROAD)
DOUGLAS COUNTY
STA. 0+32.00
TO STA. 26+36.00
RURAL 2-LANE
100% STATE
0005

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	88.0
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	249.0
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	249.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	823.0
40600300	AGGREGATE (PRIME COAT)	TON	9.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	379.0
40600990	TEMPORARY RAMP	SQ YD	925.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	706.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	103.0
40800030	AGGREGATE (PRIME COAT)	TON	1.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	90.0
44003100	MEDIAN REMOVAL	SQ FT	2,238.0
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	93.0
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	30.0
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	61.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	29.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	91.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2.0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	861.0
* 70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	62.0

FILE NAME *	USER NAME * hennessdm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\hennessdm\d0242491\050875-sht-500.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	DOUGLAS	25	4
		CHECKED -	REVISED -										
		DATE -	REVISED -										

CONTRACT NO. 70875
ILLINOIS FED. AID PROJECT