

SCHEDULE OF QUANTITIES

RAMP	DIRECTION	LANE	LENGTH	WIDTH	TYPE IV	SAWCUTS	TIE BARS	PATCHING	RRPM'S	RRPM	
								REINFORCEMENT		REMOVAL	
							3/4"				
					44200614	44213200	44213204	44213000	78100100	78300200	
			(FT)	(FT)	(SQ YD)	(FT)	(EACH)	(SQ YD)	(EACH)	(EACH)	
I-DA	I74 WB-I57 SB	RAMP	100	16	177.8	164.0	50.0	177.8	3.0	3.0	
I-DB	I74 WB-I57 NB	RAMP	180	16	320.0	244.0	90.0	320.0	8.0	8.0	
I-BD	I57 SB-I74 EB	RAMP	240	16	426.7	304.0	120.0	426.7	4.0	4.0	
I-BD	I57 SB-I74 EB	RAMP	160	16	284.4	224.0	80.0	284.4			
I-BD	I57 SB-I74 EB	RAMP	180	16	320.0	244.0	90.0	320.0			
I-BC	I57 SB-I74 WB	RAMP	40	16	71.1	104.0	20.0	71.1	1.0	1.0	
I-AC	I57 NB-I74 WB	RAMP	145	16	257.8	209.0	73.0	257.8	4.0	4.0	
I-AC	I57 NB-I74 WB	RAMP	40	16	71.1	104.0	20.0	71.1			
I-AC	I57 NB-I74 WB	RAMP	70	16	124.4	134.0	35.0	124.4			
I-AC	I57 NB-I74 WB	RAMP	100	16	177.8	164.0	50.0	177.8			
I-AC	I57 NB-I74 WB	RAMP	50	16	88.9	114.0	25.0	88.9			
I-CB	I74 EB-I57 NB	RAMP	100	16	177.8	164.0	50.0	177.8	3.0	3.0	
I-CA	I74 EB-I57 SB	RAMP	580	16	1031.1	644.0	290.0	1031.1	9.0	9.0	
I-CA	I74 EB-I57 SB	RAMP	30	16	53.3	94.0	15.0	53.3			
I-CA	I74 EB-I57 SB	RAMP	200	16	355.6	264.0	100.0	355.6			
			SUB TOTALS			3937.8	3175.0	1108.0	3937.8	32.0	32.0
			USE			3938.0	3175.0	1108.0	3938.0	32.0	32.0

78008210 - POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	
RAMP	FEET
I-DA = I-74 WB - I-57 SB	200.0
I-DB = I-74 WB - I-57 NB	360.0
I-BD = I-57 SB - I-74 EB	1160.0
I-BC = I-57 SB - I-74 WB	80.0
I-AC = I-57 NB - I-74 WB	810.0
I-CB = I-74 EB - I-57 NB	200.0
I-CA = I-74 EB - I-57 SB	1620.0
TOTAL	4430.0