

90% FEDERAL
10% STATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MACOUPIN COUNTY

MONTGOMERY COUNTY

SUMMARY OF QUANTITIES

HMA ROADWAY	SN 059-0039	SN 059-0040 SN 059-0041	HMA ROADWAY	SN 068-0052
-------------	-------------	----------------------------	-------------	-------------

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0005	0014	0014	0005	0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	68	68				
20200100	EARTH EXCAVATION	CU YD	633	633				
20200500	EARTH EXCAVATION (WIDENING)	CU YD	109	109				
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	52	43			9	
20400800	FURNISHED EXCAVATION	CU YD	178	156		20	2	
21400100	GRADING AND SHAPING DITCHES	FOOT	1,150	900			250	
* 25000200	SEEDING, CLASS 2	ACRE	0.8	0.7			0.1	
* 25100115	MULCH, METHOD 2	ACRE	0.7	0.6			0.1	
25100630	EROSION CONTROL BLANKET	SQ YD	262	262				
28000500	INLET AND PIPE PROTECTION	EACH	16	15			1	
28100207	STONE RIPRAP, CLASS A4	TON	408	378			30	
28100225	STONE RIPRAP, CLASS B3	TON	181	73				108
28200200	FILTER FABRIC	SQ YD	757	567				190
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	815	815				
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	631	631				
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	879	879				
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	1,348		1,348			
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	3,702	362		3,320		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	219.5	148.7			70.8	
40600300	AGGREGATE (PRIME COAT)	TON	1,155	782			373	
40600896	CONSTRUCTING TEST STRIP	EACH	3	2			1	
40600962	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	180	180				
40800990	TEMPORARY RAMP	SQ YD	1,841		1,108		533	
40803245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	47,063	32,916			14,147	

* SPECIALTY ITEM

FILE NAME = c:\pwwork\p\idos\co\cte\dms62217\sh-t-50.dgn	USER NAME = coxte	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 55	SECTION (59,68)RS-3, BR	COUNTY •	TOTAL SHEETS 137	SHEET NO. 4
CONTRACT NO. 72921				
ILLINOIS FED. AID PROJECT.				

• MONTGOMERY, MACOUPIN