

90% FEDERAL
10% STATE

ILLINOIS DEPARTMENT OF TRANSPORTATION				MACOUPIN COUNTY			MONTGOMERY COUNTY	
SUMMARY OF QUANTITIES				HMA ROADWAY	SN 059-0039	SN 059-0040 SN 059-0041	HMA ROADWAY	SN 058-0052
				80% FED	80% FED	80% FED	80% FED	80% FED
				20% STATE	20% STATE	20% STATE	20% STATE	20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0005	0014	0014	0005	0005
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	26,208	18,005	139		8,064	
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	28,956	19,230			9,726	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	15	15				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	107			107		
44000100	PAVEMENT REMOVAL	SQ YD	94	94				
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	19,201	5,890			13,311	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	86,605	86,605				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	128,810	71,174			57,636	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	32,909	10,478			22,431	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	108,245	108,245				
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	91,993				91,993	
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	53,327	53,327				
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	54,870	54,870				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,027	4,027				
44003100	MEDIAN REMOVAL	SQ FT	3,580	3,580				
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,043	5,043				
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	56	56				
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	40	40				
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	69	69				
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	27	8			19	
44200812	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	44				44	
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	37	37				
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	27	27				
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	43	43				
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	64				64	

FILE NAME =	USER NAME = covte	DESIGNED -	REVISED -
c:\pe_work\pmdos\covte\dms62217\sh-500.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000 / IN.		CHECKED -	REVISED -
PLOT DATE = Feb-07-2011 01:25:40PM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.I. RTE. 55	SECTION (59,68)RS-3,BR	COUNTY *	TOTAL SHEETS 137	SHEET NO. 5
CONTRACT NO. 72921			ILLINOIS FED. AID PROJECT	

* MONTGOMERY, MACOUPIN