

90% FEDERAL
10% STATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MACOUPIN COUNTY

MONTGOMERY COUNTY

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0005	0014	0014	0005	0005
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	10	4			6	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701328	L SUM	1	1				
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701408	L SUM	1	0.5			0.5	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.5			0.5	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	0.5			0.5	
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.5			0.5	
70102835	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	11	8	1	2		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	13			3	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	31,620	21,543			10,077	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	287,556	200,958			86,598	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,877	962			915	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	8,648	3,434			5,214	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,010	490			520	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	144	72			72	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13,207	12,055			1,152	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	825			825		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	825			825		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	18	18				
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	76.3	76.3				
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30	30				
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	202.8	109.2			93.6	

* SPECIALTY ITEM