

HOT-MIX ASPHALT SURFACE REMOVAL														
		PAVEMENT	LT / MED	RT/OUT	HMA SURF	HMA SURF	HMA SURF	HMA SURF	HMA SURF	HMA SURF	HMA SURF	HMA SURF	HMA SURF	HMA SURF
		WIDTH	SHOULDER	SHOULDER	REM 3/4"	REM 1 1/2"	REM 2"	REM 2 1/2"	REM 3 1/4"	REM 3 3/4"	REM 4"	REM 5"	REM-BUTT	JOINT
LOCATION		(FOOT)	(FOOT)	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
I-55 MAINLINE														
SOUTHBOUND														
STA 142+12.30	TO	STA 165+42.43	24	6									4,142.45	6,213.68
STA 165+42.43	TO	STA 170+72.68	24	6									353.50	1,414.00
STA 170+72.68	TO	STA 171+35.68	24	6	13	TO	16						143.50	168.00
STA 171+35.68	TO	STA 184+20.53	24	6									2,284.18	3,426.27
STA 184+20.53	TO	STA 186+30.92	24	6	16	TO	6						397.40	561.04
STA 186+30.92	TO	STA 195+80.94	24	6									633.35	2,533.39
STA 195+80.94	TO	STA 197+44.60	24	6			10						290.95	436.43
STA 197+44.60	TO	STA 199+54.71	24	6	16	TO	6						396.87	560.29
STA 199+54.71	TO	STA 209+04.74	24	6									633.35	2,533.41
STA 209+04.74	TO	STA 300+02.29	24	6			10						16,173.42	24,260.13
STA 300+02.29	TO	STA 500+00.00	24	6			10						35,551.48	53,327.23
STA 500+00.00	TO	STA 605+36.48	24	6			10						18,731.52	28,097.28
STA 605+36.48	TO	STA 610+66.53	24	6									353.37	1,413.47
STA 610+66.53	TO	STA 611+23.38	24	6	13	TO	16						129.49	151.60
STA 611+23.38	TO	STA 636+47.80	24	6			10						4,487.86	6,731.79
STA 636+47.80	TO	STA 638+47.63	24	6	16	TO	6						377.46	532.88
STA 638+47.63	TO	STA 648+06.69	24	6									639.37	2,557.49
STA 648+06.69	TO	STA 676+04.00	24	6			10						4,973.00	7,459.49
STA 676+04.00	TO	STA 698+00.00	24	6			10						3,668.89	5,503.33
NORTHBOUND														
STA 142+12.30	TO	STA 164+92.75	24	6									4,054.13	6,081.20
STA 164+92.75	TO	STA 174+42.78	24	6									633.35	2,533.41
STA 174+42.78	TO	STA 176+53.17	24	6	6	TO	16						397.40	561.04
STA 176+53.17	TO	STA 178+16.64	24	6			10						290.61	435.92
STA 178+16.64	TO	STA 187+66.70	24	6									633.37	2,533.49
STA 187+66.70	TO	STA 189+77.07	24	6	6	TO	16						397.37	560.99
STA 189+77.07	TO	STA 202+61.83	24	6			10						2,284.02	3,426.03
STA 202+61.83	TO	STA 203+24.94	24	6	16	TO	13						143.75	168.29
STA 203+24.94	TO	STA 208+55.11	24	6									353.45	1,413.79
STA 208+55.11	TO	STA 300+02.29	24	6			10						16,261.65	24,392.48
STA 300+02.29	TO	STA 500+00.00	24	6			10						35,551.48	53,327.23
STA 500+00.00	TO	STA 603+11.76	24	6			10						18,332.02	27,498.03
STA 603+11.76	TO	STA 613+62.39	24	6									700.42	2,801.68
STA 613+62.39	TO	STA 614+72.56	24	6	6	TO	16						208.10	293.79
STA 614+72.56	TO	STA 636+60.85	24	6			10						3,890.29	5,835.44
STA 636+60.85	TO	STA 637+17.70	24	6	16	TO	13						129.49	151.60
STA 637+17.70	TO	STA 642+47.75	24	6									353.37	1,413.47
STA 642+47.75	TO	STA 676+31.62	24	6			10						6,015.77	9,023.65
STA 676+31.62	TO	STA 698+00.00	24	6			10						3,647.79	5,471.68
MEDIAN CROSSOVERS														
STA 149+15			31 & VAR										279.02	
STA 249+40			31 & VAR										287.46	
STA 306+10			30 & VAR										274.77	
STA 444+75			30 & VAR										274.77	
STA 579+90			30 & VAR										274.77	
STA 660+30			30 & VAR										274.77	

CONTINUED NEXT PAGE

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\coxte\dms62217\067292	-sht-schedules.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 72921
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -										
	PLOT DATE = Feb-07-2011 01:56:05PM	DATE -	REVISED -										