

HOT-MIX ASPHALT SURFACE REMOVAL - CONTINUED																
LOCATION		PAVEMENT WIDTH (FOOT)		LT / MED SHOULDER WIDTH (FOOT)		RT/OUT SHOULDER WIDTH (FOOT)		HMA SURF REM 3/4"	HMA SURF REM 1 1/2"	HMA SURF REM 2"	HMA SURF REM 2 1/2"	HMA SURF REM 3 1/4"	HMA SURF REM 3 3/4"	HMA SURF REM 4"	HMA SURF REM 5"	HMA SURF REM-BUTT JOINT
								(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)
IL 138 (MT OLIVE) INTERCHANGE RAMP - CONTINUED																
RAMP C																
STA 300+00.09	TO	STA 305+30.04	1	TO	29											
STA 305+30.04	TO	STA 305+86.76														
STA 305+86.76	TO	STA 318+10.42				4		1,359.62								2,175.40
STA 318+10.42	TO	STA 319+26.46				4		128.93								499.47
RAMP D																
STA 400+23.84	TO	STA 402+11.21				4		208.19								452.51
STA 402+11.21	TO	STA 411+58.58				4		1,052.63								1,684.21
STA 411+58.58	TO	STA 412+66.39	16	TO	14											71.87
STA 412+66.39	TO	STA 413+66.57														66.79
STA 413+66.57	TO	STA 423+16.91	20	TO	1											633.56
IL 138																
STA 82+30.00	TO	STA 87+01.14	30	TO	28	10										2,565.10
STA 87+01.14	TO	STA 87+52.82	28	TO	41	10										312.95
STA 87+52.82	TO	STA 88+09.43				10										383.69
STA 88+09.43	TO	STA 88+45.09	41	TO	29	10										217.92
STA 88+45.09	TO	STA 92+77.44				10										2,353.91
STA 92+77.44	TO	STA 93+33.48														180.57
STA 93+33.48	TO	STA 93+77.09	29	TO	40											167.17
STA 93+77.09	TO	STA 93+98.90				46										111.47
STA 93+98.90	TO	STA 94+10.99				46	10									75.23
STA 94+10.99	TO	STA 94+65.77				46	10									401.72
STA 94+65.77	TO	STA 95+15.81	42	TO	40	10										339.16
STA 95+15.81	TO	STA 96+35.77				41	10									813.06
STA 96+35.77	TO	STA 98+63.09	41	TO	29	10										1,389.18
STA 98+63.09	TO	STA 98+99.91	29	TO	28	10										198.42
STA 100+99.66	TO	STA 101+36.59	28	TO	29	10										199.01
STA 101+36.59	TO	STA 101+62.67				29										141.99
STA 101+62.67	TO	STA 103+23.78	29	TO	41	10										984.56
STA 103+23.78	TO	STA 104+76.15				41										1,032.73
STA 104+76.15	TO	STA 105+26.19	40	TO	42	10										339.16
STA 105+26.19	TO	STA 105+80.96				46	10									401.65
STA 105+80.96	TO	STA 105+92.18				46										69.81
STA 105+92.18	TO	STA 106+14.92				46										116.23
STA 106+14.92	TO	STA 106+63.17	40	TO	29											184.96
STA 106+63.17	TO	STA 107+14.14				29										164.24
STA 107+14.14	TO	STA 107+47.75				29	10									145.64
STA 107+47.75	TO	STA 110+26.63				29	10									1,518.35
STA 110+26.63	TO	STA 112+18.60	29	TO	40	10										1,162.49
STA 112+18.60	TO	STA 112+65.00				40	10									309.33
SIDEROADS & ENTRANCES																
TR 395 (SN 059-0038)																
STA 46+24.48	TO	STA 46+74.48				20										166.67
STA 49+10.76	TO	STA 49+60.73				20										166.57
TOTAL								19,201	86,605	128,810	32,909	108,245	91,993	53,327	54,870	180

SHOULDER RUMBLE STRIP				LENGTH
LOCATION				(FOOT)
I-55 MAINLINE				
SOUTHBOUND OUTSIDE SHOULDER				
STA 142+12	TO	STA 165+42		2,330
STA 171+36	TO	STA 184+21		1,285
STA 195+81	TO	STA 197+45		164
STA 209+05	TO	STA 300+02		9,097
STA 300+02	TO	STA 605+36		30,534
STA 611+23	TO	STA 636+48		2,524
STA 648+07	TO	STA 676+04		2,797
STA 677+36	TO	STA 698+00		2,064
SOUTHBOUND INSIDE SHOULDER				
STA 142+12	TO	STA 300+02		15,790
STA 300+02	TO	STA 676+04		37,602
STA 677+36	TO	STA 698+00		2,064
NORTHBOUND OUTSIDE SHOULDER				
STA 142+12	TO	STA 164+93		2,280
STA 176+53	TO	STA 178+17		163
STA 189+77	TO	STA 202+62		1,285
STA 208+55	TO	STA 300+02		9,147
STA 300+02	TO	STA 603+12		30,310
STA 614+60	TO	STA 636+61		2,201
STA 642+48	TO	STA 676+32		3,384
STA 677+48	TO	STA 698+00		2,052
NORTHBOUND INSIDE SHOULDER				
STA 142+12	TO	STA 300+02		15,790
STA 300+02	TO	STA 676+32		37,630
STA 677+48	TO	STA 698+00		2,052
TOTAL				212,545

SIGNS				
LOCATION	TYPE	RELOCATE SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 1 (SQ FT)	TELESCOPING
				SUPPORT (FOOT)
IL 138				
MAINLINE				
STA 83+72	LT	KEEP RIGHT	7.25	
STA 94+76	RT	KEEP RIGHT	7.25	
STA 97+80	RT	LEFT TURN	6.19	
STA 101+82	LT	LEFT TURN	6.19	
STA 105+10	LT	KEEP RIGHT	7.25	
STA 110+64	RT	LEFT TURN	6.19	
RAMP A				
STA 120+79	RT	STOP	9	
STA 120+86	LT	STOP		9
STA 120+94	RT	STOP	9	
RAMP C				
STA 318+89	LT	STOP	9	
STA 319+05	LT	STOP		9
STA 319+05	RT	STOP	9	
TOTAL			76.3	18
TOTAL			76.3	30