

CLASS A PATCHING SCHEDULE (I-55)											
LOCATION	LENGTH	LENGTH	WIDTH	CL A	CL A	CL A	CL A	CL A	SAW CUTS	TIE BARS	PATCH REINF
	DL	PL		12"	13"	13"	14"	14"			
	(FOOT)	(FOOT)	(FOOT)	TY II (SQ YD)	TY II (SQ YD)	TY III (SQ YD)	TY II (SQ YD)	TY IV (SQ YD)			
SOUTHBOUND I-55											
STA 181+10	6.0		12.0		8.00				60.0		8.00
STA 192+20	50.0		4.0			22.22			116.0	25.0	22.22
STA 232+64	50.0		4.0			22.22			116.0	25.0	22.22
STA 240+90	25.0		4.0		11.11				66.0	13.0	11.11
STA 395+53	15.0		6.0	10.00					54.0		10.00
STA 405+95	6.0		12.0	8.00					60.0		8.00
STA 411+97	6.0		12.0	8.00					60.0		8.00
STA 431+67	8.0		12.0	10.67					64.0		10.67
STA 479+00	6.0		12.0	8.00					60.0		8.00
STA 479+68	6.0		12.0	8.00					60.0		8.00
STA 533+07	6.0		12.0				8.00		60.0		8.00
STA 536+70	8.0		12.0				10.67		64.0		10.67
STA 547+54	6.0		12.0				8.00		60.0		8.00
STA 604+29	15.0		6.0				10.00		54.0		10.00
STA 625+50	40.0		6.0					26.67	104.0	20.0	26.67
NORTHBOUND I-55											
STA 497+92	6.0		12.0		8.00				60.0		8.00
STA 554+61	6.0		12.0	8.00					60.0		8.00
STA 569+00	6.0		12.0	8.00					60.0		8.00
TOTAL				68.67	27.11	44.44	36.67	26.67	1,238.0	83.0	203.56

CLASS B PATCHING SCHEDULE (INTERCHANGE RAMPS)								
LOCATION		LENGTH (FOOT)	WIDTH (FOOT)	CL B	CL B	SAW CUTS (FOOT)	DOWEL BARS (EACH)	TIE BARS (EACH)
				11"	13"			
				TY II (SQ YD)	TY II (SQ YD)			
IL 138 INTERCHANGE								
RAMP A	OFFRAMP	6.0	16.0	10.67		60.0	16	3
RAMP B	ONRAMP	6.0	16.0	10.67		60.0	16	3
RAMP C	OFFRAMP	6.0	16.0	10.67		60.0	12	3
RAMP D	ONRAMP	6.0	16.0	10.67		60.0	12	3
IL 16 INTERCHANGE								
RAMP 1	OFFRAMP	6.0	16.0		10.67	60.0	16	3
RAMP 2	ONRAMP	6.0	16.0		10.67	60.0	16	3
RAMP 3	OFFRAMP	6.0	16.0		10.67	60.0	16	3
RAMP 4	ONRAMP	6.0	16.0		10.67	60.0	16	3
LOOP 1	ONRAMP	6.0	16.0		10.67	60.0	16	3
LOOP 2	ONRAMP	6.0	16.0		10.67	60.0	16	3
TOTAL				42.68	64.02	600.0	152.0	30.0

CONCRETE ITEMS										
LOCATION					CORRUGATED MEDIAN (SF)	CONC MEDIAN SM-6.06 (SF)	CONC SURFACE, 4" (SF)	CCC&G (FOOT)	CCC&G (FOOT)	PCC
										BASE CSE
										10" (SQ YD)
IL 138										
MAINLINE										
STA 82+58.61	TO	STA 83+67.20			524.02					
STA 83+67.20	TO	STA 87+52.82	MEDIAN			4,827.95				
STA 83+73.70	TO	STA 87+46.32	MEDIAN				745.24			
STA 87+14.14	TO	STA 87+52.59	MEDIAN						7.95	
STA 88+11.03	TO	STA 93+78.62	MEDIAN			8,681.79				
STA 88+17.53	TO	STA 93+72.12	MEDIAN				1,109.18			
STA 88+18.63	TO	STA 88+47.25	MEDIAN							2.54
STA 94+36.17	TO	STA 98+62.50	MEDIAN							429.00
STA 94+65.77	TO	STA 98+62.50	DOWELLED		3,278.00					
STA 101+36.50	TO	STA 105+58.70	MEDIAN							432.00
STA 101+36.50	TO	STA 105+19.93	DOWELLED		3,165.00					
STA 106+10.00	TO	STA 112+65.00	MEDIAN			8,235.47				
STA 106+16.50	TO	STA 112+65.00	MEDIAN				1,297.00			
RAMP A										
STA 120+83.71	TO	STA 120+97.50	ISLAND			136.88				
STA 120+83.71	TO	STA 120+98.07	ISLAND							5.62
STA 120+94.00			ISLAND				18.10	16.00		
RAMP C										
STA 319+01.05	TO	STA 319+18.52	ISLAND			328.20				
STA 319+06.28	TO	STA 319+19.31	ISLAND							2.28
STA 319+05.00			ISLAND				31.70	24.30		
TOTAL					524	6,443	22,210	3,201.2	40.3	879.4

PAVEMENT PATCHING SCHEDULE - IL 138				
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	PAVT	PAVT
			PATCH	PATCH
			12" TY II (SQ YD)	12" TY III (SQ YD)
WESTBOUND IL138				
	6.0	14.0	9.33	
	6.0	14.0	9.33	
	6.0	14.0	9.33	
EASTBOUND IL 138				
	6.0	14.0	9.33	
	6.0	14.0	9.33	
	6.0	14.0	9.33	
TR 395				
	6.0	30.0		20.00
	6.0	30.0		20.00
TOTALS			55.98	40.00

PATCHING SUMMARY													
LOCATION	CL A	CL A	CL A	CL A	CL A	CL B	CL B	PAVT	PAVT	PATCH	SAW	DOWEL	TIE
	12"	13"	13"	14"	14"	11"	13"	PATCH	PATCH	REINF	CUTS	BARS	BARS
	TY II (SQ YD)	TY II (SQ YD)	TY III (SQ YD)	TY II (SQ YD)	TY IV (SQ YD)	TY II (SQ YD)	TY II (SQ YD)	12" (SQ YD)	12" (SQ YD)	12" (SQ YD)	(FOOT)	(EACH)	(EACH)
I-55 MAINLINE	68.67	27.11	44.44	36.67	26.67						203.56	1,238.0	83.0
IL 138 INTERCHANGE RAMPS						42.68					240.0	56	12
IL 16 INTERCHANGE RAMPS							64.02				360.0	96	18
IL 138								55.98					
TR 395									40.00				
GRAND TOTAL	69	27	44	37	27	43	64	56	40	204	1,838	152	113

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -
et:\pw\work\p\dot\coxte\dms62217\067292	-sht-sched\les.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Feb-07-2011 01:57:54PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(59,68)RS-3,BR	*	137	23
CONTRACT NO.			72921	
ILLINOIS FED. AID PROJECT				