

PAVEMENT MARKING SCHEDULE														
			PAINT PAVEMENT MARKING			PREFORMED PLASTIC PAVEMENT MARKING - INLAID, TYPE B						RAISED REFLECTIVE PAVEMENT MARKERS		
SECTION		LENGTH	SOLID WHITE EDGE LINE 5"	YELLOW SKIP-DASH 5"	SOLID YELLOW LINE 5"	SOLID WHITE LINE 6"	WHITE 2 FT SKIP-DASH 6"	SOLID YELLOW LINE 8"	SOLID YELLOW LINE 12"	SOLID WHITE LINE 12"	SOLID WHITE 24"	LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
"FROM" STATION	"TO" STATION	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	EACH	EACH
84+70.00	97+62.90	1292.9	2585.8	323.2	1292.9								16	16
97+62.90	119+77.20	2214.3	4740.7		4711.8	403.1	74.1				20.9	62.4		
119+77.20	130+96.00	1118.8	2237.6	279.7	1118.8								14	14
130+96.00	138+81.73	785.7	1571.5	196.4									10	10
138+81.73 BK	139+88.70 AH													
139+88.70	249+05.00	10916.3	21832.6	2729.1									136	136
249+05.00	258+00.00	895.0	1790.0	223.8	895.0								11	11
258+00.00	261+00.00	300.0	600.0		600.0								4	4
261+00.00	270+00.00	900.0	1800.0	225.0	900.0								11	11
270+00.00	270+19.96	20.0	39.9		39.9								0	0
270+19.96 BK	270+60.46 AH													
270+60.46	286+50.00	1589.5	3179.1		3179.1								20	20
286+50.00	318+00.00	3150.0	6300.0	787.5									39	39
318+00.00	319+00.00	100.0	200.0		200.0								1	1
319+00.00	337+00.00	1800.0	3657.5		7081.2	230.0	65.5	142.9	646.7	61.6	34.6	46.8		
337+00.00	342+00.00	500.0	1000.0		1000.0								6	6
342+00.00	349+13.70	713.7	1427.4		2212.0	260.0	43.8		140.0			31.2		
349+13.70	352+65.00	351.3	702.6		1288.0				117.0					
352+65.00	361+80.00	915.0	1830.0	228.8	915.0								11	11
361+80.00	455+62.05	9382.1	18764.1	2345.5									117	117
455+62.05 BK	455+82.01 AH													
455+82.01	501+39.00	4557.0	9114.0	1139.2									57	57
501+39.00	512+60.00	1121.0	2242.0		1121.0								14	14
512+60.00	513+80.00	120.0	240.0		240.0								2	2
513+80.00	524+45.00	1065.0	2130.0	266.3	1065.0								13	13
524+45.00	732+50.94	20805.9	41611.9	5201.5									260	260
			129596.6	13945.9	27859.7	893.1	183.4	142.9	903.7	61.6	55.5	140.4	744	744
		TOTAL =		171,410		1,080	150	970	60		141	750	750	

GUTTER OUTLET SCHEDULE				
LOCATION			COMBINATION CONCRETE CURB AND GUTTER REMOVAL	GUTTER OUTLET
STATION	TO	STATION	FOOT	EACH
109+85.40	-	110+07.40	22	1
111+40.90	-	111+79.60	41	1

ESTIMATED QUANTITIES SCHEDULE									
LOCATION			COMBINATION CONCRETE CURB AND GUTTER REMOVAL	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 6.24	STONE DUMPED RIPRAP, CLASS B3	FILTER FABRIC	PAVEMENT PATCHING, TYPE II	PAVEMENT PATCHING, TYPE III	PAVEMENT PATCHING, TYPE IV
STATION	TO	STATION	FOOT	FOOT	TON	SQ YD	SQ YD	SQ YD	SQ YD
565+00.00	-	580+00.00	500	500					
584+00.00	-	585+00.00			23.9	27			
676+00.00	-	678+00.00			33.3	38			
85+00.00	-	166+50.00					100		
166+50.00	-	732+50.94					150	200	200