

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE 0005 URBAN		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5935	5935		
40600300	AGGREGATE (PRIME COAT)	TON	119	119		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1246	1246		
40600990	TEMPORARY RAMP	SQ YD	715	715		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2493	2493		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	29673	29673		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	98	98		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	39	39		
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	12	12		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	551	551		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	188	188		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	153	153		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	146	146		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1155	1155		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	193	193		
*78000100	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	257	257		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18379	18379		
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	868	868		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	217	217		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	122	122		
*88600100	DETECTOR LOOP, TYPE I	FOOT	1676	1676		
X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	512	512		
Z0012500	CONCRETE CURB REPAIR	FOOT	292	292		
	*SPECIALTY ITEM					

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -			322	(26-2)RS-2	Fayette	11	3	
PLOT SCALE = #SCALE#		CHECKED -	REVISED -			CONTRACT NO. 74459					
PLOT DATE = #DATE#		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		