

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		100% STATE 0014
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	382	382
50102400	CONCRETE REMOVAL	CU YD	17.5	17.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	18.3	18.3
50300300	PROTECTIVE COAT	SQ YD	61	61
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2950	2950
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2530	2530
50800515	BAR SPLICERS	EACH	48	48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	115	115
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6	6
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18	18
52100520	ANCHOR BOLTS, 1"	EACH	48	48
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6
70400100	TEMPORARY CONCRETE BARRIER	FOOT	616	616
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	616	616
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1576	1576
78300100	PAVEMENT MARKING REMOVAL	SQ FT	119	119
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	24	24
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1

*SPECIALTY ITEM

FILE NAME :	USER NAME : *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL#		DRAWN -	REVISED -					821	D7 BRIDGE REPAIRS 2011-1	WAYNE	23	3
PLOT SCALE : *SCALE#		CHECKED -	REVISED -		SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.			CONTRACT NO. 74485				
PLOT DATE : *DATE#		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							