

PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 8" SCHEDULE

LOCATION				LENGTH (FEET)	WIDTH (FEET)	QUANTITY (SQ. YD.)
953+99.15	TO	955+67.65	RT	168.5	6.0	112.3
953+99.15	TO	955+67.65	LT	168.5	6.0	112.3
960+21.90	TO	961+99.21	RT	177.3	4.0	78.8
960+21.90	TO	961+99.21	LT	177.3	4.0	78.8
TOTAL =						382

PAVEMENT MARKING REMOVAL SCHEDULE

LOCATION				QUANTITY (SQ. FT.)
954+49.15	TO	955+83.15	LT	11.2
955+83.15	TO	960+06.90	LT	35.3
955+83.15	TO	960+06.90	RT	35.3
960+06.90	TO	961+49.44	LT	11.9
954+48.71	TO	955+83.15	RT	11.2
960+06.90	TO	961+72.12	RT	13.8
TOTAL =				119.0

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION	LENGTH (FEET)	
954+87.15 TO 961+02.90	616.0	
TOTAL =		616.0

RELOCATE TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION	LENGTH (FEET)	
954+87.15 TO 961+02.90	616.0	
PROJECT TOTAL		616.0

PAVEMENT MARKING SCHEDULE

LOCATION	SKIP-DASH 4"	EDGE LINE 4"	QUANTITY (FOOT)
	(YELLOW)	(WHITE)	
954+49.15 TO 961+49.44	175.1	1400.6	1,575.7
TOTAL =			1,576

RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE) SCHEDULE

LOCATION	QUANTITY (EACH)	
SN 096-0062	5	
PROJECT TOTAL		5