

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 90% FEDERAL 10% STATE		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	638	638		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	7	7		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	110	110		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	4	4		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	21	21		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3229	3229		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	28353	28353		
50105220	PIPE CULVERT REMOVAL	FOOT	783	783		
54213450	END SECTIONS 15"	EACH	62	62		
54213453	END SECTIONS 18"	EACH	10	10		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	839	839		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	162	162		
64200105	SHOULDER RUMBLE STRIPS	FOOT	62332	62332		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	73564	73564		
	*SPECIALTY ITEM					

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILE#		DRAWN -	REVISED -					770	.	Shelby	24	3	
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		
	PLOT DATE = *DATE*	DATE -	REVISED -		CONTRACT NO. 74504								