

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED. 20% STATE	0005 80% FED 10% STATE 10% VERNON	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED. 20% STATE	0005 80% FED 10% STATE 10% VERNON
21400100	GRADING AND SHAPING DITCHES	FOOT	1400	1400		70300100	SHORT TERM PAVEMENT MARKING	FOOT	7200	7200	
28000500	INLET AND PIPE PROTECTION	EACH	4	4		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	202468	202468	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	14	14		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	17473	17473	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17		*78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	50617	50617	
40600300	AGGREGATE (PRIME COAT)	TON	80.7	80.7		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	247	247	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2198	2198		*78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	32	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1191	1191		*78200430	GUARDRAIL MARKERS, TYPE C	EACH	16	16	
40600990	TEMPORARY RAMP	SO YD	286	286		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	247	247	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	4424	4424		■ X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	2475	2475	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	78	78		Z0018300	DRAINAGE STRUCTURE REPAIR	EACH	1	1	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	52787	52787		■ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18	18	
44004250	PAVED SHOULDER REMOVAL	SO YD	5		5	● Z0076600	TRAINEES	hour	500	500	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SO YD	49	49							
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1127	1127							
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	5		5						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1522	1210	312						
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1							
50800105	REINFORCEMENT BARS	POUND	68	68							
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	1	1							
54248510	CONCRETE COLLAR	CU YD	2	2							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	6	6							
550A4500	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	226	226							
55101900	STORM SEWER REMOVAL 48"	FOOT	226	226							
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE B GRATE	EACH	1	1							
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4							
67100100	MOBILIZATION	L SUM	1	1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1							
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1							
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1							
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1							

● QQ42
 *SPECIALTY ITEM
 ■ NON-PARTICIPATING
 100% STATE

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			322	(24,25)RS-3	MARION	27	3	
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. 3 OF 27 SHEETS STA. _____ TO STA. _____		CONTRACT NO. 76B76			
	PLOT DATE = #DATE#	DATE - ---	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					